

ABSTRACT

Name of Work:- Repairs to 25 ton cap hoist of RBC Service gate of size 2.5 x 2.35mtr @ Wadgaon Dam project.

Sr. No.	Description	Quantity	Rate	Amount
1	Dismantling and Refitting of hoist assembly - 1 No. Complete job including cost of Material (sundry) material and labour charges.. (As per Rate Analysis -1)	1 Job.	15551.47 <u>15397.50</u>	15551.47 <u>15397.50</u>
2	Repairs to 25 Ton Hoist of Service gate of size 2.5 x 2.35mtr @ Wadgaon Dam project. @ Wadgaon Dam (As per Rate Analysis -2)	Quantity	1 No.	160086 ✓
	Lower Flange Plate 22 mm thk, Dia.- 380mm	1		
	Upper Flange Plate 18 mm thk, Dia. - 380mm	1		
	Motor Foundation Bolt M12 with 1 nos nut, Length - 75mm	4		
	Lower flange coupling bolt M20 bolt with 2 nos nut, length - 150mm	8		
	M18 Bolt for bearing Pedastal with 2 nos nut, length - 100mm	16		
	SKF Thrust Bearing (51330)	1		
	M. P. Grade No. 150 Grease	10		
	Total Weight in Kg -	44.93		
3	Transportation of Fabricated Material by 4MT cap tempo. (As per Rate Analysis -3)	2 Trip	3554.09 ✓	7108.18 ✓
182745.65			SubTotal :	<u>182591.2</u>