

Works Detail's

Name of work : Repairs To Fuel Line Assembly Rewinding, Wheel Gressing etc of Tata Tipper MH-20-CU No.201

Sr. No.	Description	Qty	Unit	Rate	Amount
1	2	3	4	5	6
	General Repairs Of Tata Tipper MH-20-CU No.201 with cost of labour charges as below				
1	Complete fuel line opening, cleaning, checking, brazing and refitting	1	Job		
2	Fuel tank opening, clening, brazing and refitting	1	Job		
3	Radiator Chockup removing by removing by cleaning all the tubes, soldering the tubes with top and bottom removing and refitting	1	Job		
4	Silencer/ miffler repairing by removing, cleaning and refitting with welding work	1	Job		
5	Starter Armature rewinding with material	1	Job		
6	Steering unit overhauling	1	Job		
7	Front Wheel gressing including oil seal chaning	2	Job		
8	Rel Wheel hub gressing including oil seal changing/no	2	Job		
9	King pin overhauling and refitting	1	Job		
10	Foront spring lcaf assly, removing, dismentaling, recambering and refitting assly	1	Job		
11	front mudguard damaged and rusted inner and outer wheel house new pieces welding, patching and finishing	2	Job		
12	Rear mudguard damaged and rusted inner and outer wheel house new pieces welding, patching and finishing	2	Job		
13	Front bumper removing repairing by welding straightening, denting and refitting	1	Job		
14	Door locks removing repairing and refitting door adjusting and setting / no	2	Job		
15	Branding on vehicle and front and rear number plate flooring pieces patching and welding	1	Job		
16	Complete Flooring rusted portion cutting and new flooring pieces parching and welding	1	Job		
17	Complete seat and back rest aushioning with coir foam 4" with 2 foam 2" with best quality rexinne cover	1	Job		
				Total Rs:	
				Add CGST @9% Rs:	
				Add SGST @9% Rs:	
				Grand Total Rs:	


Deputy Engineer
Mechanical Subdivision No.2
Dharashiv