महाराष्ट्र शासन
जलसंपदा विभाग
कार्यकारी अभियंता, यांत्रिकी विभाग क्र. 2, स्वारगेट, पुणे 411 037
दूरध्वनी क्र :- 020-24266011
Email ID :- eemd123@gmail.com
G. S. T. No. :- 27AAALI0006N3Z8

जा. क्र. यांविक्र.2,पुणे 37 / भांडारशाखा / 2206 / सन 2026 दि. २०/११/२०२६

दरपत्रकासाठी सूचना

विषय :- कार्यकारी अभियंता यांत्रिकी विभाग क्र.2, स्वारगेट पुणे 37 यांच्या कार्यालयाकरिता पिण्याच्या व वापरणेच्या पाण्याची टाकी पुरवठा करणे व बसविणे बाबत.

संदर्भ :- विभागीय कार्यालयाचे मंजूर अंदाजपत्रक यांविक्र.2/तांशा/अंदाजपत्रक/2208/ सन 2026, दि. 02.11.2026

कार्यकारी अभियंता, यांत्रिकी विभाग क्र. 2, पुणे 37 यांचे अखत्यारीतील विषयांकीत कामासाठी नोंदणीकृत / सदर कामाचे अनुभव असणा-या अभिकरणांकडून सिलबंद लिफाफयासोबत जोडलेल्या कामाचा तपशिल, नियम व अटीनूसार दरपत्रक मागविण्यात येत आहे. दरपत्रकाच्या सिलबंद लिफाफयाच्या वरिल बाजूस दरपत्रक असा उल्लेख करुन उपरोक्त विषयाचा व या कार्यालयाचा उपरोक्त पत्र क्र. नमुद करण्यात यावा.

सदरचे दरपत्रक हे **दिनांक** २७/११/२०२६ **ठिक** 4.00 वाजेपर्यंत या कार्यालयास प्राप्त होणे आवश्यक आहे. दरपत्रकामधील दर हे दरपत्रक उघडल्यापासून 90 दिवस बंधनकारक राहतील.

सोबत :- कामाचा तपशिल

नियम व अटी :-

1. दरपत्रकातील दर मागितलेल्या युनिटप्रमाणे दयावेत.
2. नियमानूसार आयकर, वस्तु व सेवाकर तसेच संबंधी शासन निर्देशानूसार इतर कर कपात करण्यात येतील.
3. दरपत्रके हे छायाचित्र प्रतीवर लिहिलेले स्विकारले जाणार नाही.
4. दरपत्रकातील दर हे दर पत्रक उघडल्यापासून 90 दिवस ग्राहय धरले जातील.
5. काम पूर्ण व समाधानकारक झाल्यानंतर धनादेशाने बिलाचे पैसे 30 दिवसांत अदा केले जातील. **(निधी उपलब्ध असेल तर).**
6. दरपत्रके ही त्याच दिवशी शक्य झाल्यास उघडले जातील.
7. कोणतही दरपत्रक स्विकारणे किंवा नाकारणे याबाबतचा हक्क निम्नस्वाक्षरीकार यांनी राखून ठेवला आहे.

(रा. भा. कुलकर्णी)
कार्यकारी अभियंता
यांत्रिकी विभाग क्र. 2, पुणे 37

प्रत :- विभागीय कार्यालय नोटीस बोर्ड व महायांत्रिकी संकेतस्थळ.
प्रत :- विभागीय कार्यालय तांत्रिक शाखा यांना माहितीसाठी.

SCHEDULE

Name of Work: - Supplying Water tanks with all necessary arrangement in the Executive Engineer , Mech Div No 2 , Swargate Pune 37 for the year 2026-27

S/N.	PARTICULARS	QTY.	UNIT	RATE	AMOUNT
	Material				
1	Providing and fixing H.D.P container one piece moulded water tank made out of high density polythyler and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet,outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters .Fitting of two water tank = 1000x2 = 2000 ltr (water tank capacity =1000 Ltr each)	2000.00	Ltr		
2	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum,including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed,dewatering, preparing the bed for the foundation and necessary back filling, ramming, wateringincluding shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Manual Means Total Measurment 3 Mtr x1.5 Mtr x 0.15 Mtr = 0.675 Cu Mtr	0.68	One Cubic Metre		
3	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.3.0 meters x 1.5 meters (Area = 4.5 Sqm) and a height of 0.6 meters. Hence 3x1.5x0.3= 1.35 Cu.Mtr	1.35	Cubic Mtr		
4	Providing and laying in situ / ready mix M-15 plain cement concrete of trap/granite/quartzite/ gneiss metal for cast in citu piers, abutment, returns, wings etc.including provision of "V" shaped false joints to form suitable panels on the faces to approve design with compacting by vibrating and curing complete, including plywood/steel form work centering (excluding dewatering by means of pump) and including bailling out water and curing finishing in CM 1:3 etc. complete. as directed by engineer in charge basic rate shall be increased for height above 5.00 m in followinh manners(a) Height upto 5 M. (With Concrete Mixer)With fine agreegates of required specifications (VSI sand finely washed etc)i) Height up to 5 m, normal rate.ii) Height 5 to 7.50 m, add 5 percent extra over basic rate.iii) Height 7.50 to 10 m, 7.50 percent extra.iv) Over 10 m Height, add 10 percent extra for every 2.50m rise.Required 2 Platforms Over and Under Brick work = 0.675x2 = 1.35 Cub Mtr	1.35	Cubic Mtr		

5	Providing and fixing on walls/ ceiling/ floor 15 mm dia. UPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00	One RunningMetre		
6	Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area .	250.00	Square Mtr		
				Material Cost	
				GST 18 %	
				Total Amount Rs.	
				Say	

Executive Engineer,
Mechanical Division No 2 ,
Swargate, Pune-37.