

Work Detail's

Name of Work : Repair & reconditioning of Engine Assembly of Tata Sumo No. MH-25, C-6387

Sr. No.	Description	Qty	Unit	Rate	Amount
1	2	3	4	5	6
I	Cost of Spare Charges				
1	SET CON ROD BRG 4DL TC - 254703990158	1	No.		
2	MAIN BRG SET 0.010 U/S - 2547MB100111	1	No.		
3	SET MAIN BRG RS2 - 2547MB200111	1	No.		
4	CON ROD BUSH - 254703153442	4	No.		
5	SET PISTON RINGS - 254703990176	1	No.		
6	VALVES SET 4DLNA - 254701150139 / 254701150138	1	No.		
7	SET THRUST WASHER (2.52) - 254703120106	1	No.		
8	KIT ENG OVERHAUL GASKETS - 254700990105	1	No.		
9	KIT ENGINE OVERHAUL SEALS - 254700990106	1	No.		
10	VALVE SEAT INSERT IN STD - 254701153414	4	No.		
11	ENGINE SUPPORT FRT LH - 254722123708	1	No.		
12	ENGINE SUPPORT FRT RH - 254722123709	1	No.		
	Total Spares Cost				0.00
II	Cost of Labour Charges				
1	Complete engine dismantling from chassis of machine/vehicle and installing on machine/vehicle after overhauling including crane charges (E/01)	1	Job		
2	Engine Cylinder Block main line boring (E/02)	1	Job		
3	Engine Cylinder Block surface grinding (E/05)	1	Job		
4	Engine Cylinder Block boring and honing (E/06)	1	Job		
5	Engine Cylinder head valve seat removing & new fitting(E/12)	1	Job		
6	Engine Crank Shaft rear main oil seal replacing (E/21)	1	Job		
7	Engine Crank Shaft bend checking and bend removing(E/22)	1	Job		
8	Engine Crank Shaft crack testing (E/23)	1	Job		
9	Engine foundation replacing per No. (E/40)	2	Job		
10	Front wheel hub greasing including oil seal changing / No (W/06)	2	Job		
11	Rear wheel hub greasing including oil seal changing / No. (W/07)	2	Job		
	Total Labour Charges Cost				0.00
	Total A				0.00
I	Cost of Spare Charges				
1	Assly Door Hynge LH , 269872300115	1	No.		
2	Assly Door Hynge RH , 269872300116	1	No.		
3	Assly Floor Mat ,269868800104	1	No.		
4	Grab handle (Door) 265172506316	1	No.		
	Total Spares Cost				0
II	Cost of Labour Charges				
1	Door locks removing, repairing and refitting. Door adjusting and setting/ No.(BD/10)	1	Job		
2	Radiator chock up removing by cleaning all the tubes, soldering the tubes with top & bottom removing and refitting (E/46)	1	Job		
	Total Labour Charges Cost				0
	Total B				0
	Total Spare Cost(A) + Labour Charges(B)				0.00
	CGST@9%				0.00
	SGST@9%				0.00
	Grand Total				0.00
	Say Total				0.00


 (P.L. Hadule)
 Deputy Engineer