



GOVERNMENT OF MAHARASHTRA
WATER RESOURCE DEPARTMENT
BUDGETARY OFFER No.TS2/9 for2014-15

Executive Engineer ,Vishnupuri PumpHouse Division,Nanded (Phone no.02462-260738) Email-vphdn@rediffmail.com invites “Budgetary Offer” for Estimation purpose for supply of below listed spares from manufactures/Authorised Dealers/Traders/Experienced reputed contractors.

Sr.No	Description of Spares	Rate/No.
1.	Supply, erection, testing & commissioning of 6.6KV VCB 1600A HT panel comprising of 2Nos. transformer power receiving + 1Nos. Buscoupler + 14Nos. Motor feeder suitable for 850HP motor + 1nos. spare motor feeder + 2Nos. capacitor feeder + 1Nos. Auxiliary transformer feeder 315KVA.	1job .
	<ul style="list-style-type: none">a. 11KV, 1600A, 40KA 1 SEC, VCB, DRAW OUT & ISOLATION Horizontalb. CT 3core. 5P10 / PS / Metering.c. PT with fuse.d. Numerical O/c & E/f relay, DC Fail relay, Under voltage relay, Stand by earth fault relay, Master trip relay, TCS relay.e. 12 window alarm system.f. Indication lamp and metering with MFM. Buscoupler - <ul style="list-style-type: none">a. 11KV, 1600A, 40KA 1 SEC, VCB, DRAW OUT & ISOLATION Horizontalb. Indication lamp. Motor feeder - <ul style="list-style-type: none">a. 11KV, 630A, 25KA 1 SEC, VCB, DRAW OUT & ISOLATION Horizontalb. CT 2core. one protection + one metering.c. Numerical O/c & E/f relay, motor protection relay, Master trip relay, TCS relay.d. 12 window alarm system.e. Indication lamp and metering with MFMf. Surge arrestor. Capacitor feeder - <ul style="list-style-type: none">a. 11KV, 630A, 25KA 1 SEC, VCB, DRAW OUT & ISOLATION Horizontal	

	<ul style="list-style-type: none"> b. CT 2core. one protection + one metering. c. CBCT. d. Numerical O/c & E/f relay, capacitor protection relay, Master trip relay, TCS relay. e. 12 window alarm system. f. Indication lamp and metering with MFM 	
2	Supply, erection, testing & commissioning of LT Panel 1 comprising of 1Nos. Incomer ACB 630A + Outgoing - 100A SFU - 4nos. + 63A SFU - 8nos. + 32A SFU - 14nos. with all Protection, metering & Indication equipments	1 Set
3	Supply, erection, testing & commissioning of LT Panel 2 comprising of 3Nos. Incomer MCCB 200A + 200A COS - 2nos. + Outgoing - 200A MCCB - 6nos. + 63A SFU - 4nos. + 100A SFU - 4nos. with all Protection, metering & Indication equipments	1 Set
4	Supply, erection, testing & commissioning of LT Panel 3 comprising of 2Nos. Incomer MCCB 100A + 100A COS - 1nos. + Outgoing - 35HP Star delta starter - 3nos. + 15HP Star delta starter - 7nos. + 63A SFU - 4nos. with all Protection, metering & Indication equipments.	1 Set
5	Supply, erection, testing & commissioning of Dual FCBC – 110V /30A suitable for 200 AH Lead Acid Battery and load of 10A with integral DCDB of 6 nos. MCB of 16A each. I/P : 415V AC +/-10% 50Hz O/P : 110VDC /30A with all Protection, metering & Indication equipments	1 Set
6	Supply, erection, testing & commissioning of 110V/200AH Lead acid stationary tubular battery	1 Set

Interested vendors are requested to submit the Budgetary offer for the supply of above mentioned materials. The interested vendors can visit the site to inspect required material / job work and accordingly they should quote their lowest offer. The above Budgetary offer should reach to this office on or before date:- 05/09 /2014 by email only. The offer should be sent including all taxes and mentioned Validity & delivery Period

Please Note:- Budgetary offer is invited only for the estimation purpose. It does not give any assurance regarding floating of tender or otherwise

**Executive Engineer,
Vishnupuri Pump House Division
Nanded**

Letter no.VPHDN/TS2/1991 dt.27/08/2014
office of Executive Engineer,
Vishnupuri Pump House Division,
Sinchan Bhavan Workshop
Nanded-431605

copy submitted to S.E mechanical circle, Nanded for favor of information please
copy forwarded to Deputy Engineer, Electrical SubDiv(VP) Asarjan Hq. Nanded for
information