

E-Mail – [tembhumeunit@gmail.com](mailto:tembhumeunit@gmail.com)  
जा.क्र./टेंउसिंयांविप/लेशां-२/ १५७२ /२०१४

Phone – (02164) 271142  
कार्यकारी अभियंता,  
टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक,  
ओगलेवाडी, कराड यांचे कार्यालय  
दिनांक:- २०/१०/२०१४

प्रति,  
जिल्हा माहिती अधिकारी,  
जिल्हा माहिती कार्यालय,  
३ रा मजला, नवीन प्रशासकीय इमारत,  
सातारा. ४१५ ००१ (फोन नं. ०२१६२-२३७४४०)

**विषय :- जाहीरात प्रसिध्दीस देणेबाबत.**

महोदय,

सोबत जोडलेली जाहिरात वृत्तपत्रात प्रसिध्द करण्यासाठी पाठविण्यात येत आहे. कृपया ती नेमून दिलेल्या तारखेला किंवा तत्पूर्वी प्रसिध्दीस द्यावी, ही विनंती.

- १) कार्यालयाचे नाव, पत्ता व दुरध्वनी क्रमांक : कार्यकारी अभियंता, टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक, ओगलेवाडी, कराड पिन :- ४१५१०५, फोन नं : (०२१६४) २७११४२.
- २) जाहीरात प्रसिध्द होण्याचा अंतिम दिनांक : दिनांक ३१/१०/२०१४ अथवा तत्पूर्वी
- ३) प्रसिध्दी कोणत्या स्तरावर आवश्यक (प्रादेशिक/जिल्हा पातळीवर) : जिल्हा स्तरावर (सातारा Region)
- ४) जाहीरातीचे बील कोणाच्या नावे पाठवावयाचे : कार्यकारी अभियंता, टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक, ओगलेवाडी, कराड
- ५) जाहीरात किती वृत्तपत्रात प्रसिध्द करावयाची व किती वेळा. : एक “क” वर्ग मराठी दैनिक व एका साप्ताहिक वृत्तपत्रात एकाचवेळी फक्त एकवेळा.
- ६) किती वेळा जाहिरात प्रसिध्द करावयाची आहे. : एकवेळा.

आपला विश्वासू

सोबत :- जाहिरातीच्या ४ प्रती.

कार्यकारी अभियंता  
टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक,  
ओगलेवाडी, कराड

प्रत :- मा.अधीक्षक अभियंता, यांत्रिकी मंडळ ,कोल्हापूर यांना माहितीसाठी व वेबसाईट प्रसिध्दीसाठी सविनय सादर.

## जलसंपदा विभाग ( यांत्रिकी )

### अंदाजपत्रकीय दरपत्रके मागविण्यासाठीची दरपत्रके

कार्यकारी अभियंता टेंभू उपसा सिंचन यांत्रिकी व विद्युत पथक, कोयना सायडींग, ओगलेवाडी, कराड ४१५१०५. दुरध्वनी क्र.२७११४२ हे खाली दर्शविलेल्या कामाकरिता नोंदणीकृत यांत्रिकी कंत्राटदाराकडून व मुळ साहित्य निर्मात्यांकडून कार्यालयीन कामासाठी अंदाजपत्रकीय दरपत्रके मागवित आहेत. संबंधीतांनी हि जाहिरात प्रसिद्ध झाल्यापासून सात दिवसांच्या आत आपली अंदाजपत्रकीय दरपत्रके कार्यालयीन वेळेत सादर करावीत. सादर कामाच्या बाबीचा सविस्तर तपशील [www.mahayantriki.gov.in](http://www.mahayantriki.gov.in) या वेबसाईट वर उपलब्ध आहे.

अ.क्र	कामाचे नांव	परिमाण	दर रुपये
1	Budgetary Offer required for estimate purpose of manufacturing, providing Testing supplying at site etc. complete job of ID -Ø 1100 mm Rubber Expansion Joint of natural rubber with copper coated steel wire or solid endless ring embedded in the carcass.	10 Nos.	
2	Mfg. providing ,supply of HRC& HT panel fuses for 6.6 KV; 415/500V;90 amp; 319 KVAR Capacitor	50 Nos.	
3	Mfg. providing ,supply of Capacitor Cubicles of 113 KVR 6.6KV ,29.7 A, 3 ph, etc. complete job for Tembhu Lift Irrigation scheme stage IA, - etc. complete job	6 Nos. each	
4	Mfg. providing supply, Testing, erection commissioning etc,complete job for Temp scanner unit assly consisting of 10 points icroprocessor base Temperature scanner suitable for working with 3 wire system PT 100 type RTDS	25 Nos.	
5	Mfg; providing supply, erection commissioning of electronic pressure gauge digital type with solenoid switch for measuring pressure up to 15 bar	22 Nos.	
6	Budgetary offer for job work of carrying out repair work of 35/5 cap EOT crane 1 No at Tembhu stage III pump house	4 Nos.	
7	Erection assembly testing trial, commissioning etc. compile job of m & p make VT pump of designed parameters for parameters for punadi lift irrigation scheme stage 3 including labour machinery tool & tackles sandry material etc. complete.	1 Nos.	
8	Shifting, Erection assembly, testing, trial commissioning etc. compete job of HT panel 6.6 KV 3 Nos with incomer & feeder, cabeling for panel with operation for 45 days etc. complete job for punadi lift irrigation scheme stage 3 including labour operator electronic tools & tackles etc. complete	1 Nos.	
9	(Providing Supplying, Fabrication) fitting of Ø 100 mm & 150 mm MS pipe, Ball valve, NRV short & long bend, elbow, necessary flanges Sluice valve etc. complete job for cooling arrangement of Tembhu Stage 1A ,3A & 3B for motor cooling arrangement.-.	6 Nos.	
10	Mfg. providing,Supply,erection,commissioning etc. complete of HT panel 6.6KV with Fuses, Tripical,Trip relay for above set KV for 1500 KW HT motor etc. complete job	6 Nos.	
11	To carry out job work required for repairing of 6.6 Kv,1505 Kw, 50HZ, three phase induction motor no 4 & 11 of Tembhu LIS stage IA.Replacing brg DE& NDE, Replacing connection lead up to winding necessary hardwares, servicing of slator & rotor by means of oven heat treatment assly of preparing all inspection by means of special tool & tackles instrument with skilled staff preparing test report erection of motor at site testing & commissioning handling & forwarding charges etc. complete job for Tembhu stage IA LIS Scheme @ Tembhu Karad	2 Nos.	

वरील कामासाठी सादर केलेली अंदाजपत्रकीय कार्यवाहीसाठी असून प्रत्यक्ष कामाच्या आदेशाशी त्याचा काही संबंध नाही.

कार्यकारी अभियंता  
टेंभू उपसा सिंचन यांत्रिकी व विद्युत पथक,  
ओगलेवाडी, कराड

ssNO/ME/TLIM/AB-2/ 1572 / 2014

Executive Engineer  
Tembhu Lift Irrigation  
Mechanical & Electrical Unit  
Koyana Siding Oglewadi,  
Karad - 415105  
Date; - 20 / 10 /2014

To,

M/s 1] -----  
2] -----  
3] -----

Sub: - Regarding Budgetary Offers.

Dear Sir,

budgetary offer For the following work are invited from Manufacturers/contractors having experience of the said work for estimate purpose.

The Budgetary Offers Should be Submitted to this office Within Working Hours.

Sr.no.	Description	Rate	Amt.
1.	Budgetry Offer required for estimate purpose of manufacturing, providing Testing supplying at site etc. complete job of ID - $\phi$ 1100 mm Rubber Expansion Joint of natural rubber with copper coated steel wire or solid endless ring embedded in the carcass. Having design pressure 10 kg /cm <sup>2</sup> ; Test pressure 15 kg/cm <sup>2</sup> ;Test vaccum 700 mm of Hg, Bursting pressure 20kg/cm <sup>2</sup> , flange od:- 1355 mm; flange thickness 28mm; width -350mm; having axial compression & expansion-12mm; lateral deflection 10mm; no.of Holes 32 Nos of $\phi$ 44mm on pcd 1270mm; etc. complete job- for M&P make VT pump at Tembhu Lift Irrigation Scheme IA,IB,IIIA,-Qty-10 Nos.		
2	Mfg. providing ,supply of HRC& HT panel fuses for 6.6 KV; 415/500V;90 amp; 319 KVAR Capacitor suitable for operating & short timecurrent of 21.8 KA for one second etc. complete job for Tembhu Lift Irrigation scheme stage IA,IIIA;- -339 KVAR 90 amp for IB-384 KAVR 70 Amp & for IIIB-348 KVAR 70 Ampres etc. complete job qty :- 50 Nos each.		
3	Mfg. providing ,supply of Capacitor Cubicles of 113 KVR 6.6KV ,29.7 A, 3 ph, etc. complete job for Tembhu Lift Irrigation scheme stage IA, - etc. complete job qty :- 6 Nos each.		
4	Mfg. providing supply, Testing, erection commissioning		

	etc,complete job for Temp scanner unit assly consisting of 10 points microprocessor base Temperature scanner suitable for working with 3 wire system PT 100 type RTDS for the range of 0 <sup>o</sup> C to 200 <sup>o</sup> C with indicating Accuracy of 0.25% full scale (Fs) tic & resolution of 0.1 <sup>o</sup> c suitable operation of 220V +- 10% , 50 Hz AC supply with alarm ready; 7 segment LED display ; suitable for programming data with key board; speed 1 see onwords etc.complete job for M&P, & kirloskar make VT pump at Tembhu Lift Irrigation scheme stage – 1A,IIIA,1B’ Qty 25Nos each.		
5	Mfg; providing supply, erection commissioning of electronic pressure gauge digital type with solenoid switch for measuring pressure up to 15 bar with necessary mechanical & electrical fittings etc. complete job for Tembhu Lift Irrigation Scheme stage IIIA-Qty 22Nos.		
6	Budgetary offer for job work of carrying out repair work of 35/5 cap EOT crane 1 No at Tembhu stage III pump house includes overhauling of all travels M.S. Fabricated helical gear box-4 nos [Main hushing -1No Auxiliary Hushing -1 No C.T. -1 no L.T.-1no] clearing rust removing on the all D.S.L line Applying grease to drum bush L.T. Wheel C.T. Wheels etc. carrying out necessary electrical repair work etc at site.		
7	Erection assembly testing trial, commissioning etc. compile job of m & p make VT pump of designed parameters for parameters for punadi lift irrigation scheme stage 3 including labour machinery tool & tackles sandry material etc. complete. 1 Nos		
8	Shifting, Erection assembly, testing, trial commissioning etc. complete job of HT panel 6.6 KV 3 Nos with incomer & feeder, cabeling for panel with operation for 45 days etc. complete job for punadi lift irrigation scheme stage 3 including labour operator electronic tools & tackles etc. complete. Job 1 Nos		
9	(Providing Supplying, Fabrication) fitting of Ø 100 mm & 150 mm MS pipe, Ball valve, NRV short & long bend, elbow, necessary flanges Sluice valve etc. complete job for cooling arrangement of Tembhu Stage 1A ,3A & 3B for motor cooling arrangement.-6 Nos.		
10	Mfg. providing,Supply,erection,commissioning etc. complete of HT panel 6.6KV with Fuses, Tripical,Trip relay for above set KV for 1500 KW HT motor etc. complete job – 6 Nos.		

11	To carry out job work required for repairing of 6.6 Kv,1505 Kw, 50HZ, three phase induction motor no 4 & 11 of Tembhu LIS stage IA. Replacing brg DE& NDE, Replacing connection lead up to winding necessary hardwares, servicing of slator & rotor by means of oven heat treatment assly of preparing all inspection by means of special tool & tackles instrument with skilled staff preparing test report erection of motor at site testing & commissioning handling & forwarding charges etc. complete job for Tembhu stage IA LIS Scheme @ Tembhu Karad Qty – 2 Nos.		
----	--	--	--

Thanking you

Yours Faithfully,  
Executive Engineer,  
Tembhu Lift Irrigation & Electrical Unit,  
Ogalewadi – Karad.

Copy submitted to the Superintending Engineer, Mechanical Circle , Kolhapur, for Information & Necessary action Please.

