

No cg4 / ts / bud. Offer/

/ of 2015

office of the

Executive Engineer,
Chief Gate Erection Unit No 4
Aurangabad
Dt.

To,

Reputed Electrical / Mechanical Contractors

Subject :- Budgetary offers for Fabrication, supply & Erection of Cabin type Canopy for Central drive unit of Radial Gate, Hoist system at Lower Dudhana Project

Dear Sir,

Budgetary offers for Fabrication, supply & Erection of Cabin type Canopy for Central drive unit of Radial Gate Hoist system at Lower Dudhana Project as per the notice attached are herewith called hereby from Contractors registered with Mechanical Organization stating lowest possible rates .

Please Note

- 1) The Budgetary offers are called for only estimation purpose. Submission of offer Does not means that order of work will be given to the contractor .
- 2) The rates quoted in Budgetary offers should be inclusive all taxes & levies
- 3) The site where cabin is to be erected is available for inspection on Lower Dudhana Project on any working day , within working hours , with prior permission of project authority..
- 4) Offers can be submitted on or before **27/07/2016**, directly to the office of the Executive Engineer, Gate Erection Unit No 4 Aurangabad or by E- Mail on the address **eeunit4@gmail.com**

Thanking You & hoping your response.

Your's Faithfully

Executive Engineer
Chief Gate Erection Unit No 4
Aurangabad

Notice for Budgetary Offer

Name of Work :-Manufacturing & Providing Cabin type. Canopy for central drive unit of 42.0 ton capacity Hoist system of Radial Gates at Lower Dudhana Project

Sr No.	Description of Work	Qty	Remarks
1	2	3	4
1	<p>Manufacturing, Providing & Erecting Canopy type.cabin withoutflooring for Central Drive Unit of 42.0 T capacity Hoisting arrangement for Radial Gates size 12.0 x8.0 Mtr- 20Nos at Lower Dudhana Project including extension of Hoist Bridge of 0.92 mtrx1.45 mtr atleft & 0.92 mtr x0.5 mtr at right of cabin. Size of cabin –Main Frame walls 4.0mtr x3.2mtrx2.5mtr high below roof,Roof size 4.2.0 mtr x3.4mtr , 4 side slope type of hight 0.3 mtr,allMain Frame walls made of Calcium Silicate Boards of 10 mm thick\Bolted to M.S.Chanells, with one windows of size 0.6 x0.5 mtr With toughened Glass 6 mm thick fitted in suitable rubber Bedding, at 3 sides main frame & Base supports &vetical supports of M.S.Channel 75 x40 mm, Roof of Calcium Silicate Boards of 10.0 mm thick,supports of M.S.Channel 75 x40 mm,Gap of 100 mm between walls &roof, roof extended so as to protect rain , Moisture entering the cabin, complete cabin (walls,roof, supports etc painted with anticorrosive rust proof synthetic enamel paint of good quality, cabin provided with one door of size 1.1 mtr x2.0mtr with locking arrangement (lock & key)at 3 sides, cabin should be provided with hook for lifting arrangement, holes for passing of Line Shafts at appropriate places (total cabin weight should be appx.1200.00 Kg) etc complete at Lower Dudhana Project including cost of labour, materials, machining, sundries, fabrication, transportation erection & painting, all taxes &laviesetc at site etc complete job.</p>	20 Jobs	Rate / Job

Executive Engineer
Chief Gate Erection Unit No 4
Aurangabad

Notice for Budgetary Offer

Name of Work :-Manufacturing & Providing Cabin type. Canopy for central drive unit of 42.0 ton capacity Hoist system of Radial Gates at Lower Dudhana Project

Sr No.	Description of Work	Qty	Remarks
1	2	3	4
1	Manufacturing, Providing & Erecting Canopy type.cabin without flooring for Central Drive Unit of 42.0 T capacity Hoisting arrangement for Radial Gates size 12.0 x8.0 Mtr-20Nos at Lower Dudhana Project including extension of Hoist Bridge of 0.92 mtrx1.45 mtr at left & 0.92 mtr x0.5 mtr at right of cabin. Size of cabin –Main Frame walls 4.0mtr x3.2mtrx2.5mtr high below roof, Roof size 4.2.0 mtr x3.4mtr , 4 side slope type of height 0.3 mtr, all Main Frame walls made of M.S.Sheet 2.5 mm thick , with one windows of size 0.6 x0.5 mtr With toughened Glass 6 mm thick fitted in suitable rubber Bedding, at 3 sides main frame & Base supports & vertical supports of M.S.Channel 75 x40 mm, Roof of Calcium Silicate Boards of 10.0 mm thick, supports of M.S.Channel 75 x40 mm, Gap of 100 mm between walls & roof, roof extended so as to protect rain , Moisture entering the cabin, complete cabin (walls, roof, supports etc painted with anticorrosive rust proof synthetic enamel paint of good quality, cabin provided with one door of size 1.1 mtr x2.0mtr with locking arrangement (lock & key) at 3 sides, cabin should be provided with hook for lifting arrangement, holes for passing of Line Shafts at appropriate places (total cabin weight should be appx.1700.00 Kg) etc complete at Lower Dudhana Project including cost of labour, materials, machining, sundries, fabrication, transportation, erection & painting, all taxes & lavies etc at site etc complete job.	20 Jobs	Rate / Job

Executive Engineer
Chief Gate Erection Unit No 4
Aurangabad

E Mail eeunit4@gmail.com

Fax (0240)2334602

जा.क्र. मुद्दाउप -४/तां-१ / बजेटरी ऑफर /निम्नदुधना/

/२०१६ कार्यालय
कार्यकारी अभियंता
मुख्य द्वार उभारणी पथकक्र. ४
औरंगाबाद
दि.

प्रति,

मा. अधीक्षक अभियंता
यांत्रिकी मंडळ (उ सं)
नांदेड

विषय :- अर्थसंकल्पीय देकार मागवण्याबाबतचीनोटीस योत्रिकी संघटनेच्या वेबसाईटवर प्रकाशितकरणे बाबत.

या विभागांतर्गत द्वार उभारणीउप विभाग ४ ब , माजलगाव अंतर्गतनिम्नदुधना प्रकल्पावरील वक्रद्वारांच्या ४२.० टनक्षमतेच्या उच्चालक व्यवस्थेतील सेंट्रलड्राईव्ह युनिटच्या संरक्षणासाठी व सुलभ परिरक्षण व हाताळणीसाठी केबीन उभारणीचेकाम हाती घ्यावयाचे आहे. त्याकामाचे अंदाजपत्रक बनवण्यासाठी यांत्रिकी मंजूरदरसूचीच्या बाहेरील बाबींचेदर माहित करूनघेण्यासाठी यांत्रिकी मंजूरदरसूचीमध्ये समाविष्ट नसलेल्या साहित्याचे दरविविध अभिकरणांकडून अर्थसंकल्पीय देकार मागवून माहित करूनघेणे आवश्यक आहे.

तरीत्यासाठीकृपया या पत्रासोबती अर्थसंकल्पीय दर मागविणे बाबतचीनोटीस योत्रिकी संघटनेच्या वेबसाईटवर प्रकाशितकरण्यात यावी विनंती.

माहितीस्तव वपूढील कार्यवाहीस्तव सविनय सादर.

सहपत्रे—दोन

कार्यकारी अभियंता
मुख्य द्वार उभारणी पथकक्र. ४
औरंगाबाद