

Estimate

Name of work :- Supplying, erecting, testing and commissioning of earth mat for Pump House
at Bordinala Lift Irrigation Scheme, Tal. Chandur Bazar Dist- Amravati.

Sr. No.	Item of Work	Unit	Qty	Rate	Amount Rs
1	Item No.1:- Supplying and erecting M.S.Flat 50 x 10 mm as per design of eathmat. iron work, sheet metal work consisting of CRCA sheets, various sections of iron, plates, chequered plates, rods, bars, MS pipes, etc. for panel board or any other purpose with bending, cutting, drilling and welding complete erected at the position with necessary materials duly painted with one coat of red oxide and two coats of enamel paint to match the switchgears or as per directions by the authority.	kg	1547	195.30	302129.10
2	Item No.2:- Supplying and erecting GI FLAT of high purity required size used for earthing on wall and/or any other purpose with necessary GI clamps fixed on wall painted with bituminous paint with joints required. As per specification no EA-EP.	kg	1621	233.10	377855.10
3	Item No.4:- Drilling 40 mm dia holes in masonry or concrete structure with providing and fixing 0.5 M long G.I. pipeline for pressure grouting including all material, labour cost and machinery charges, etc. complete.	Rmt	126	1205.00	151830.00
Total					831814.20
Add 18% GST					149726.56
Total					981540.76
Say Rs.					981541.00


In Word Rs. Nine lakh eighty one thousand five hundred forty one only.

Prepared by



S. S. Wankhade
Sectional Engineer (Elect.)

Checked by


(R. G. Thakare)

Deputy Engineer
Gate Mfg and Erection
Sub Division No 2 Akola


Deputy Engineer

Lift Irrigation Mechanical &
Electrical sub-Dn. No. 1 Bhandara.

Executive Engineer
Mechanical Division
Akola

Sanctioned Estimate No.

EE/MD/AK/2022

Sanction for Rs. 9,81,541/- (Rs Nine) lakh
eighty one thousand five hundred forty one only



Executive Engineer
Mechanical Division
Akola