


Repairing of Head Regulator, CR cum Escape Gates of Giroli & Deoli Branch Canal of Lower Wardha Project under Executive Engineer, Lower Wardha Project Division, Wardha

Sr.No.	Description	Quantity	Rate	Amount
ABSTRACT				
A	Repairing of Head Regulator of size 0.45x0.45 mtr of Narayanpur Minor 1 -1 No. & Poti Sub Minor 1- 1 No. on Khangaon Distributory (Ref- RA-1)	2.00	/No	17280.029
B	Repairing of Head Regulator of size 0.6x0.6 of Khangaon Minor 3 -1 No. on Khangaon Distributory, Sonagaon Minor 1 -1 No. on Deoli Sub-minor & Dhotra Minor -1 No. (Ref- RA-2)	3.00	/No	26095.072
C	Repairing of Escape Gate of size 2.7x2 mtr- 1 No. @ RD 15300 mtr on Deoli Branch Canal			
1	Dismantling and replacing Pedastal Bearings / Pedastal assembly of 15 MT Cap. Screw Stem Hoist - 1 No, complete job with cost of sundry material and labour charges. (Including New Material charges) (Ref- RA-3)	1.00	/Set	12178.580
2	Dismantling and replacing Single Thrust Ball Bearing of 15 MT Cap. Worm and worm wheel type Screw Stem Hoist - 1 No,Applying M.P. Grease to square threaded portion of stem rod and thrust ball bearing complete job with cost of sundry material and labour charges (Including New Material charges) (Ref- RA-4)	1.00	/Set	66473.150
3	Straightening of Stem Rod - 1 No. of Canal Gate of size above 0.90 x 0.90 Mtr to 1.5x1.5 (size 2.7 x2.0, 2x3.5, 1.2x 1.2) Mtr by using hydraulic press machine. complete with machinery charges with leads & lifts at site etc complete. (Ref- RA-5)	1.00	/No	3339.060
4	Cleaning of square threaded and v- threaded portion of Stem rods by Cleaning agent and applying M. P.Grease to threaded portion of Canal Gate of size above 0.90 x 0.90 Mtr to 1.5x1.5 (2.7x 2) (2x 3.5) Mtr - 1 No. Complete with cost of material and labour charges with leads & lifts at site etc complete, (Ref- RA-6)	1.00	/No	3524.900
5	Dismantalling and fitting new Stem nut - 1 No. of Hoist of Canal Gate of size above 0.90 x 0.90 Mtr. to 1.5x1.5 Mtr. Complete with cost of material, sundry material and labour charges. (Ref- RA-7)	1.00	/No	42849.270
D	Repairing of Head Regulatory Gate of size 2.0x3.5 mtr- 2 No. of Deoli Branch Canal & Giroli Branch Canal			
1	Dismantling and replacing Pedastal Bearings / Pedastal assembly of 15 MT Cap. Screw Stem Hoist - 1 No, complete job with cost of sundry material and labour charges. (Including New Material charges) (Ref- RA-3)	1.00	/Set	12178.580
2	Dismantling and replacing Single Thrust Ball Bearing of 15 MT Cap. Worm and worm wheel type Screw Stem Hoist - 1 No,Applying M.P. Grease to square threaded portion of stem rod and thrust ball bearing complete job with cost of sundry material and labour charges (Including New Material charges) (Ref- RA-4)	2.00	/Set	66473.150
3	Straightening of Stem Rod - 1 No. of Canal Gate of size above 0.90 x 0.90 Mtr to 1.5x1.5 (size 2.7 x2.0, 2x3.5, 1.2x 1.2) Mtr by using hydraulic press machine. complete with machinery charges with leads & lifts at site etc complete. (Ref- RA-5)	1.00	/No	3339.060
4	Cleaning of square threaded and v- threaded portion of Stem rods by Cleaning agent and applying M. P.Grease to threaded portion of Canal Gate of size above 0.90 x 0.90 Mtr to 1.5x1.5 Mtr - 1 No. Complete with cost of material and labour charges with leads & lifts at site etc complete, (Ref- RA-6)	2.00	/No	3524.900

No.	Description	Quantity	Rate	Amount
5	Dismantalling and fitting new Stem nut - 1 No. of Hoist of Canal Gate of size above 0.90 x 0.90 Mtr. to 1.5x1.5 Mtr. Complete with cost of material, sundry material and labour charges. (Ref- RA-7)	1.00	/No	42849.270
E	Repairing of Head Regulatory Gate of size 1.2x1.2 mtr- 2 No. on Deoli Sub Branch Canal @ RD 38080 mtr of Deoli Branch Canal & also Repairing of CR Cum Escape Gate of size 1.2x1.2 mtr- 2 No. @ RD 1500 mtr on Deoli Sub Branch Canal			
1	Dismantalling and fitting Thrust Bearing - 1 No. of Hoist of Canal Gate of size above 0.9x0.9 Mtr to 1.5x1.5 (size 1.2x 1.2)Mtr. Complete with cost of material, sundry material and labour charges with leads & lifts at site etc complete, (Ref RA-8)	4.00	/Set	19298.070
2	Cleaning of square threaded and v- threaded portion of Stem rods by Cleaning agent and applying M. P. Grease to threaded portion of Canal Gate of size above 0.90 x 0.90 Mtr to 1.5x1.5 (2.7x 2) (2x 3.5) Mtr - 1 No. Complete with cost of material and labour charges with leads & lifts at site etc complete, (Ref RA-6)	4.00	/No	3524.900
3	Dismantalling and fitting new Stem nut - 1 No. of Hoist of Canal Gate of size above 0.90 x 0.90 Mtr. to 1.5x1.5 Mtr. (Ref- RA-9)	1.00	/No	17318.379
D	Repairing of Head Regulator Gate of size 2.5x1.5 mtr- 1 No. @ Khangaon Distributory on Giroli Branch Canal			
1	Dismantling and replacing Pedastal Bearings / Pedastal assembly of 15 MT Cap. Screw Stem Hoist - 1 No, complete job with cost of sundry material and labour charges. (Including New Material charges) (Ref- RA-3)	2.00	/Set	12178.580
2	Dismantling and replacing Single Thrust Ball Bearing of 15 MT Cap. Worm and worm wheel type Screw Stem Hoist - 1 No, Applying M.P. Grease to square threaded portion of stem rod and thrust ball bearing complete job with cost of sundry material and labour charges (Including New Material charges) (Ref- RA-4)	2.00	/Set	66473.150
3	Replacement of New stem rod of 63 mm dia - 4 Mtr long - 1 No. of Canal Gate of size above 0.9x0.9 Mtr to 1.5x1.5 Mtr. Complete including cost of material and machining charges with leads & lifts at site etc complete. (Ref- RA- 10)	1.00	/No	11771.550
E	Surface Preparation, Providing & Applying Primer Red Oxide Paint in two coats & anticorrosive coal tar black paint IS 290-1961 in two coats (Ref- RA-11)	1.00	/No	80030.000
F	Crane Escort Moc Crane- 8E (8T Cap) Charges for Gate, Hoist Loading & unloading of Material @ Deoli & Giroli Branch Canal Nimn Wardha canal Site. Escort Moc Crane- 8E (8T Cap) (Ref- RA-12)	4.00	/Day	3888.500
G	Transportation from Wardha to Nimn Wardha Deoli Giroli Branch Canal Site (Ref RA-13)	5.00	Trip	2908.800
	TOTAL CHARGES (A) :-			827386.515
	Add 1% Insurance charges:			8273.865
	Gst 18 %:-			148929.573
	Total chrages			984589.953
	Say Total chrages			984590.000

Estimate Prepared by me

S. M. Karambe
Sect. Engineer


Deputy Engineer
Mechanical Engineering Workshop
Sub Division No 3, Wardha

Sanction Estimate No. 132
MEW DN./NGP/TS/Dt. 26/12/2024 Sanctioned
for Rs. 9,84,590/- (Rs. Nine

Lakh Eighty Four Thousand Five Hundred Ninty only.


Executive Engineer
Mechanical Engineering Workshop
Division, Sadar, Nagpur



महाराष्ट्र शासन
जलसंपदा विभाग

कार्यकारी अभियंता यांचे कार्यालय,

पत्ता : कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, सदर, नागपूर

E-mail : eemewdngp@yahoo.in

Phone No. 0712-2981048

निविदा सूचना क्र. - २३(तीसरी वेळ)/ सन २०२४-२५

महाराष्ट्र राज्याच्या राज्यपालांच्या वतीने कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, सदर, नागपूर, महाराष्ट्र शासन हे सक्षम निविदाकारांहुन खालील कामाकरीता निविदा मागवित आहे. महाराष्ट्र शासन जलसंपदा विभाग शासन निर्णय क्रमांक संकिर्ण/१११७/प्र.क्र.१०४/१७/यांत्रिकी दिनांक १४.०३.२०१८ अन्वये खालील कामांकरिता निविदा सादर करणारे कंत्राटदार, जलसंपदा विभागातील यांत्रिकी संघटनेकडे पंजकृत असणे आवश्यक नाही. सदर निविदा सूचना जलसंपदा (यांत्रिकी) विभागाच्या वेबसाईटवरील क्र. www.mahayantriki.gov.in या संकेस्थळावर बघावयास मिळेल. निविदा स्वीकारण्याचा अथवा नाकारण्याचा अधिकार कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर, यांनी राखून ठेवला आहे. अट असलेली निविदा स्वीकारली जाणार नाही. सदर निविदा सुचनेमध्ये काही बदल होत असल्यास विभागीय कार्यालयाच्या सूचना फलकावर / www.mahayantriki.gov.in उपलब्ध करून देण्यात येईल.

१) कामाचे नाव : निम्न वर्धा मुख्य कालव्यावरून उगमित गिरोली शाखा कालवा व देवळी शाखा कालवा यांचे मुख्य विमोचक, वितरीकेवरील लघू कालव्यावरील द्वारे दुरुस्ती कामे. (रु.827387/-)

निविदेची किंमत रुपये :- Rs. ८,२७,३८७/- जीएसटी वगळून

कोरी निविदा प्रपत्राची किंमत Rs. १,०००/-

रु. १८०/- Goods and Services Tax (GST) To be paid by Reverse charge mechanism

(भरणा केलेली पावती निविदा उघडण्याचा दिवसापर्यंत कार्यालयात जमा करणे बंधनकारक राहिल. अन्यथा लिफाफा क्र. १ मध्ये अपात्र करण्यात येईल)

निविदा विक्रीचा कालावधी :- दि.२३.०४.२०२५ (११.०० वाजेपासून) ते दि.३०.०४.२०२५ (१८.०० वाजेपर्यंत)

निविदा सादर करण्याचा अंतिम कालावधी :- दि. २३.०४.२०२५ (११.०० वाजेपासून) ते दि.०५.०५.२०२५ (१८.०० वाजेपर्यंत)

निविदा उघडण्याचा कालावधी :- दिनांक ०७.०५.२०२५ ११.०० पासून

कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर
यांच्या कार्यालयात.

जा.क्र. ८५० /लेखा शाखा.२/निविदा सूचना क्र २३(तीसरी वेळ)/ २०२४-२५

कार्यालय, कार्यकारी अभियंता
यांत्रिकी अभियांत्रिकी कर्मशाळा
विभाग, नागपूर
दिनांक : १५.४.२०२५

Sd/-

(वि.रा.प्रधान)

कार्यकारी अभियंता,
यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग,
नागपूर



GOVERNMENT OF MAHARASHTRA

WATER RESOURCES DEPARTMENT

Mechanical Engineering Workshop Division,
OFFICE OF THE EXECUTIVE ENGINEER

ADDRESS :- EXECUTIVE ENGINEER MECHANICAL ENGINEERING WORKSHOP DIVISION,
SADAR NAGPUR-01

Email Id :- eemewdngp@yahoo.in

Telephone No. 0712-2981048

CORRIGENDUM

Read :- Tender Notice no.22/2024-25 (तीसरी वेळ)

Ref :- मा.विभागीय आयुक्त, नागपूर विभाग, नागपूर यांचे जा.क्र.सा.प्र.शा./कार्या.५(२)/प्र.क्र. ०६/ २०२५/ कावि. ८४/ २०२५ दि. १८ / फेब्रुवारी -२०२५ (यांचे सुधारीत आदेश : अक्षयतृतीया दि.30/4/2025 संपूर्ण नागपूर जिल्हा स्थानिक सुट्टी)

Name of Work : निम्न वर्धा मुख्य कालव्यावरुन उगमित गिरोली शाखा कालवा व देवळी शाखा कालवा यांचे मुख्य विमोचक वितरीकेवरील लघु कालव्यावरील द्वारे दुरुस्ती कामे.

१) निविदा विक्रीचा कालावधी दिनांक 23/4/2025 (११.०० वाजेपासुन) ते दि.30/04/2025(१८.०० वाजेपर्यंत)
ऐवजी

निविदा विक्रीचा कालावधी दिनांक 23/04/2025 (११.०० वाजेपासुन) ते दि. 02/05/2025(१८.०० वाजेपर्यंत)

२) निविदा सादर करण्याचा कालावधी दि.23/4/2025(११.०० वाजेपासुन) ते दि.05/05/2025 (१८.०० वाजेपर्यंत)
ऐवजी

निविदा सादर करण्याचा कालावधी दि.23/04/2025 (११.०० वाजेपासुन) ते दि.07/05/2025(१८.०० वाजे पर्यंत)

३) निविदा उघडण्याचा कालावधी दि. 07/05/2025 (१४.०० वाजेनंतर)
ऐवजी

निविदा उघडण्याचा कालावधी दि.09/05/2025 (१४.०० वाजेनंतर)

(V.R. Pradhan)

Executive Engineer

Mechanical Engineering Workshop Division,
Nagpur

NO. ४९६ / Tender/AB / 2024-25 dated 22/4/2025
Office of the
Executive Engineer Mechanical
Engineering Workshop Division Nagpur

Copy : सुचना फलकावरील व्यापक प्रसिध्दीसाठी.