

महाराष्ट्र शासन

जलसंपदा विभाग

कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर

E-mail : eemewdngp@yahoo.in Phone No. 0712-2981048

निविदा सूचना क्र. १२ / सन २०२६ -२७

महाराष्ट्र राज्याच्या राज्यपालांच्या वतीने कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर. महाराष्ट्र शासन हे सक्षम निविदाकारांनुन खालील कामा करीता निविदा मागवित आहे. महाराष्ट्र शासन हे सक्षम निविदाकारांनुन खालील कामाकरीता निविदा मागवित आहे. महाराष्ट्र शासन, जलसंपदा विभाग, शासन निर्णय क्रमांक संकिर्ण / १११७/ प्र.क्र. १०४ / १७/ यांत्रिकी दिनांक १४.०३.२०१८ अन्वये खालील कामांकरिता निविदा सादर करणारे कंत्राटदार, जलसंपदा विभागातील यांत्रिकी संघटनेकडे पंजिकृत असणे आवश्यक नाही. सदर निविदा सूचना जलसंपदा (यांत्रिकी) विभागाच्या वेबसाईट वरील www.mahayantriki.gov.in या संकेत स्थळावर बघावयास मिळेल. निविदा स्वीकारण्याचा अथवा नाकारण्याचा अधिकार कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर. यांनी राखून ठेवला आहे. अट असलेली निविदा स्वीकारली जाणार नाही. सदर निविदा सुचनेमध्ये काही बदल होत असल्यास विभागीय कार्यालयाच्या सूचना फलकावर [/www.mahayantriki.gov.in](http://www.mahayantriki.gov.in) उपलब्ध करून देण्यात येईल.

कामाचे नाव : Repair to Radial Gate no.5 of size 12 x 5.5 mtr - 1 no by replacing new wire rope and repairs to Goliath Crane @ Erai Project Dist Chandrapur

(कोरा निविदा प्रपत्राची किंमत Rs. १,००० /- (रु. १८०/- Goods and Services Tax (GST) भरणा केलेली पावती निविदा उघडण्याचा दिवसा पर्यंत कार्यालयात जमाकरणे बंधनकारक राहिल. अन्यथा लिफाफा क्र. १ मध्ये अपात्र करण्यात येईल.)

कामाची किंमत : - रु. 250228/- ((Excluding GST + Insurance)

जिल्हा : चंद्रपुर जिल्हा

- १) निविदा दस्तऐवज विक्री प्रारंभ व समाप्त दिनांक व वेळ :- दि. १४/७/२०२६ सकाळी ११.०० वा. पासून ते दि. २१/०७/२०२६ संध्याकाळी १८.०० पर्यंत (कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा , विभाग नागपूर यांचे कार्यालयात ऑफलाईन निविदा विक्री)
- २) निविदा दाखल करण्याची सुरुवात व अंतिम दिनांक व वेळ :- दि. १४/०७/२०२६ सकाळी ११.०० वा. पासून ते दि. २३ /०७/२०२६ संध्याकाळी १८.०० पर्यंत
- ३) निविदा तांत्रिक देकार उघडण्याचे ठिकाण, दिनांक व वेळ :- दि. २४/०७/२०२६ रोजी दुपारी १४.०० वा. कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा , विभाग नागपूर यांचे कार्यालयात , उघडण्यात येतील. (शक्य झाल्यास)

जावक क्र. 1431 /लेखा-१/ निविदा-१२/ २०२६-२७ दिनांक : 13/07/2026

(वि. स. प्रधान)

कार्यकारी अभियंता
यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग,

नागपूर

प्रत - मा. अधीक्षक अभियंता, यांत्रिकी मंडळ, नागपूर यांना माहितीसाठी सविनय सादर.

प्रत - भांडारा शाखा / विभागीय कार्यालय सूचना फलकावरील व्यापक प्रसिध्दीसाठी.

SCHEDULE - B

Name of Work - Repair of Radial Gate no .5 of size 12 x 5 mtr - 1 no which Includes Fixing new wire rope of Dia 24 mm 75 mtr length in 4 no of falls , confirming to IS 2266 and repairs to 16 MT Goliath crane @ Erai Dam Project Dist . Chandrapur under Executive Engineer , Civil Maintenance Unit No. 2 Chandrapur.

Sr. No.	Description of Job	Qty	Unit	Rate	Amount
1	Dismantalling and Replacing old damaged Brake Drum Rubber Bushes and Bolts of Coupling - 18 No. (200 mm - 1 set & 150 mm 2 Set) by new one of 16 MT Cap Goliath Crane , including cost of material , sundry material and labour charges with leads and lifts at site etc complete. As per drawings specifications and or instructions of concern in charge	1	No	5893.35	5893.35
2	Dismantaling and Replacing old damaged Brake Coil - 3 no (200 mm - 1 no & 150 mm - 2 nos) by new one of 16 MT Cap Goliath Crane., including cost of material , sundry material and labour charges with leads and lifts at site etc complete as per drawings , specifications and or instructions of concern in charge.	1	No	17331.60	17331.60
3	Diismataling and Replacing old damaged Brake Liner - 3 nos (200 mm- 1 no & 150 mm - 2 nos) by new one of 16 MT Cap Goliath Crane , including cost of material , sundry material and labour charges with leads and lifts at site etc complete , as per drawings, specifications and or instructions of concern in charge.	1	No	5009.60	5009.60
4	Draining of old oil from RGB - 3 nos(0:600- 1 no & 0:400 - 2 nos) Filling with new gear oil GX 90 - 13 Ltr, Cleaning Gear train by removing old grease , Applying M.P. Grease - 6 Kg to Gear train , Pedastal , Drum axle .etc to 16 MT Goliath Crane	1	No	9641.46	9641.46
5	Handling Charges of 6 pieces of 12 x 1 mtr Stoplog gate / RG gate for repairs to radial gate considering lowering , lifting and stacking on platform / on storing arrangement. (Require 6 nos stoplog pieces for repair)	6	Job	5085.35	30512.10
6	Under Water Inspection and Cleaning of gate slot due to presence of debris and deposits settled on sill beam to facilitate smooth working of stoplog Gate in Slot , Considered one days per gate , as deposite setteled o sill beam need some chipping work under water.	1	Job	60650.50	60650.50
7	Dismantaling of damaged wire rope , wire rope socket of 20 MT cap hoist - 1 no. Fixing new wire rope of Dia 24 mm - 75 mtr length in 4 no of falls , confirming to IS 2266 of R.G. 12 5.5 mtr.	1	No.	117989.21	117989.21

8	Transportation of sundry material by Mahindra Bolero	2	Trip	1599.84	3199.69
				Total	250227.50
				Say (₹)	250228.00
				Excluding GST + Insurance	

(In Words Rs. Two Lakh Fifty Thousand Two Hundred & Twenty Eight Only)

**Executive Engineer
Mechanical Engineering
workshop Division, Nagpur**