

महाराष्ट्र शासन
जलसंपदा विभाग

कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर

E-mail : eemewdngp@yahoo.in Phone No. 0712-2981048

निविदा सूचना क्र. १२ / सन २०२६ -२७

महाराष्ट्र राज्याच्या राज्यपालांच्या वतीने कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर. महाराष्ट्र शासन हे सक्षम निविदाकारांनुन खालील कामा करीता निविदा मागवित आहे. महाराष्ट्र शासन हे सक्षम निविदाकारांनुन खालील कामाकरीता निविदा मागवित आहे. महाराष्ट्र शासन, जलसंपदा विभाग, शासन निर्णय क्रमांक संकिर्ण / १११७/ प्र.क्र. १०४ / १७/ यांत्रिकी दिनांक १४.०३.२०१८ अन्वये खालील कामांकरीता निविदा सादर करणारे कंत्राटदार, जलसंपदा विभागातील यांत्रिकी संघटनेकडे पंजिकृत असणे आवश्यक नाही. सदर निविदा सूचना जलसंपदा (यांत्रिकी) विभागाच्या वेबसाईट वरील www.mahayantriki.gov.in या संकेत स्थळावर बघावयास मिळेल. निविदा स्वीकारण्याचा अथवा नाकारण्याचा अधिकार कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर. यांनी राखून ठेवला आहे. अट असलेली निविदा स्वीकारली जाणार नाही. सदर निविदा सूचनेमध्ये काही बदल होत असल्यास विभागीय कार्यालयाच्या सूचना फलकावर [/www.mahayantriki.gov.in](http://www.mahayantriki.gov.in) उपलब्ध करून देण्यात येईल.

कामाचे नाव : Repair of Radial Gate no.5 of size 12 x 5 mtr - 1 no which Includes Fixing new wire rope of Dia 24 mm 75 Mtr. length in 4 no. of falls, confirming to IS 2266 and repairs to 16 MT Goliath crane @ Erai Dam project . Dist Chandrapur under Executive Engineer , Civil Maintenance Unit No.2 , Chandrapur Thermal Power Generation Plant Chandrapur.

(कोरा निविदा प्रपत्राची किंमत Rs. १,००० /- (रु. १८०/- Goods and Services Tax (GST) भरणा केलेली पावती निविदा डघडण्याचा दिवसा पर्यंत कार्यालयात जमाकरणे बंधनकारक राहिल. अन्यथा लिफाफा क्र. १ मध्ये अपात्र करण्यात येईल.)

कामाची किंमत : - रु. 250228/- ((Excluding GST + Insurance)

जिल्हा : चंद्रपुर जिल्हा

- १) निविदा दस्तऐवज विक्री प्रारंभ व समाप्त दिनांक व वेळ :- दि.१४/७/२०२६ सकाळी ११.०० वा. पासून ते दि २१/०७/२०२६ संध्याकाळी १८.०० पर्यंत (कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा , विभाग नागपूर यांचे कार्यालयात ऑफलाईन निविदा विक्री)
- २) निविदा दाखल करण्याची सुरुवात व अंतिम दिनांक व वेळ :- दि. १४/०७/२०२६ सकाळी ११.०० वा. पासून ते दि. २३ /०७/२०२६ संध्याकाळी १८.०० पर्यंत
- ३) निविदा तांत्रिक देकार उघडण्याचे ठिकाण, दिनांक व वेळ :- दि. २४/०७/२०२६ रोजी दुपारी १४.०० वा. कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा , विभाग नागपूर यांचे कार्यालयात , उघडण्यात येतील. (शक्य झाल्यास)

जावक क्र. ११३१/लेखा-१/निविदा-१२/२०२६-२७

दिनांक : १३/७/२०२६

sd/-
(वि. रा. प्रधान)

कार्यकारी अभियंता
यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग,
नागपूर

ABSTRACT

Repair of Radial Gate no.5 of size 12x5mtr -1 nos which Includes Fixing new wire rope of Dia 24 mm 5 Mtr length in 4 No of falls, confirming to IS 2266 and repairs to 16MT Goliath crane @ Erai Dam Project Dist. Chandrapur under Executive Engineer, Civil Maintenance Unit No. 2, Chandrapur Thermal Power Generation Plant Chandrapur.

Sr. No.	Description	Qty	Unit	Rate	Unit (Rs/Job)	Amount
1	Dismantalling and Replacing old damaged Brake Drum Rubber Bushes and Bolts of Coupling - 18 No. (200 mm Ø - 1 set & 150 mm Ø - 2 Set) by new one of 16 MT Cap Goliath Crane. , including cost of material, sundry material and labour charges with leads & lifts at site etc complete, as per drawings, specifications and or instructions of concern in charge As Per Rate Analysis - 1	1	no.	5893.35	/no.	5893.35
2	Dismantaling and Replacing old damaged Brake Coil - 3 No. (200 mm Ø - 1 No. & 150 mm Ø - 2 NO.) by new one of 16 MT Cap Goliath Crane. , including cost of material, sundry material and labour charges with leads & lifts at site etc complete, as per drawings, specifications and or instructions of concern in charge As Per Rate Analysis - 2	1	no.	17331.60	/no.	17331.60
3	Dismantaling & Replacing old damaged Brake Liner - 3 No. (200 mm Ø - 1 No. & 150 mm Ø - 2 No.) by new one of 16 MT Cap Goliath Crane. , including cost of material, sundry material and labour charges with leads & lifts at site etc complete, as per drawings, specifications and or instructions of concern in charge As Per Rate Analysis - 3	1	no.	5009.60	/no.	5009.60
4	Draining of Old Oil from RGB - 3 Nos. (O:600 - 1No. & O:400 - 2 Nos.) Filling with new gear oil GX 90 - 13 Ltr, Cleaning Gear train by removing old grease, Applying M.P. Grease - 6 Kg to Gear train, Pedastal, Drum axle. etc to 16 MT Goliath crane As Per Rate Analysis - 4	1	no.	9641.46	/no.	9641.46
5	Handling charges of 6 pieces of 12 x 1 Mtr Stoplog gate/RG gate for repairs to radial gate considering lowering, lifting & stacking on platform / on storing arrangement. (Require 6 nos stoplog pieces for repair) As Per Rate Analysis - 5	6	Job	5085.35	/Job	30512.10

	Description	Qty	Unit	Rate	Unit (Rs/Job)	Amount
6	Under Water Inspection and Cleaning of gate slot due to presence of debris and deposits settled on sill beam to facilitate smooth working of stoplog Gate in Slot. Considered one days per gate, as deposit settled on sill beam need some chipping work under water. As Per Rate Analysis - 6	1	Job	60650.50	/Job	60650.50
7	Dismantling of damaged wire rope, wire rope socket of 20 MT cap hoist - 1 No . Fixing new wire rope of Dia 24 mm - 75 Mtr length in 4 No of falls, confirming to IS 2266 of R.G. 12 x 5.5 m As Per Rate Analysis - 7	1	no.	117989.21	/no.	117989.21
8	Transportation of sundry material by Mahindra Bolero.. As Per Rate Analysis - 8	2	Trip	1599.84 1745.28	/Trip	3199.68 3490.56
2,50,227.5						Total
						250518.38
2502.18						Add 1 % Insurance :-
						2505.18
45040.95						Add 18% GST
						45093.31
2,97,770.7						Grand Total :-
						298116.87
2,97,771/-						Round Up
						298117.00

Total Rs. Two Lakh Ninety Eight Thousand One Hundred Seventeen Only.
 Seven Seven Seventy One



 Deputy Engineer

Mechanical Engineering Workshop
 Subdivision No.1, Nagpur.

Sanction Estimate No. 35/2026-27

MEW DN/NGP/TSID/13/07/2026 Sanctioned

for Rs. 297771/- (Rs. Two Lakh Ninety Seven Thousand Seven hundred & Seventy one only.)


 Executive Engineer

Mechanical Engineering Workshop
 Division, Sadar, Nagpur.