

ABSTRACT

Name of work : - Fitting of NRV to delivery pipeline & welding of cracked portion of rising main pipe line near manifold at Ghungashi LIS stage - 1 Dist.Akola during 2025-26

S.N	Description of work	Qty		Rate Rs.	Amt Rs.
1	Item No.1 Welding of crack portion of rising main by welding circular over rising main near manifold .The job includes machinery & labour. Dia.1400 mm Thick 8 mm	4.45	mtr	1154	5135 5135.3
2	Item No.2.Alingment of Delivery pipe line by removing NRV & REJ ,delivery pipe & fitting after completing alignment of delivery pipe with welding work				
	1.REJ - Labour Charges for Removing & Fitting Rubber Expansion Joint / Dismantle joint/ Metallic Expansion Joint with gasket changing having P.N-1.0 & 1.6 . This include replacing of gasket, all tools & tackles,welding,machinery Dia 900 mm Qty 2 nos	2	no	6431 12826	12862 25652
	2.NRV - Labour charges for removing and refitting of Non return valve having P.N-1.0 & 1.6 rating from pipe line for repairs.This include replacing of gasket, all tools & tackles,welding,machinery.Dia 900 mm Qty 2 nos	2	no	12845	25690
	3.Providing rubber Gasket EPDM For Pipe Dia 900 mm	8	no	2532	20256
3	Item No.03 M.S pipe patch welding on delivery pipe near NRV for proper fitting of NRV				
	Welding in all positions with required number of runs, for M. S. pipes internally and / or externally including gauging wherever necessary, fixing appurtenances and other accessories in connection with pipe laying work as per specification.Del pipe dia 900 mm Thick 10 mm Del pipe qty.2 nos.,Weld joint 4 nos.	11.3	mtr	1414	15984 15978.20
4	Item No.4 Lowering & Laying MS pipe				
	Lowering, laying in position to correct line and level including M. S. specials with / without any outcoating such as distance pieces, straps, bends, tapers, etc. on pedestals or chairs upon formation. The rate to include loading, unloading, hoisting, marginal cutting wherever required, assembling and tack welding, and transportation upto 500M etc. complete.Del pipe dia 900 mm Thick 10 mm Del pipe qty.2 nos.	2	mtr	1488	2976
5	Item No.05.Transportation from Akola to Ghungashi LIS & back with To & Fro distance <i>add 1% wwc on rate 50.79</i>	100	km	51.298 50.79	5129.80 5079
				Total	100772
				Adding GST @ 18 %	18139
				Total	118911

(Rs.One Lac Eighteen Thousand Nine Hundred Eleven Only)

Sanctioned Estimate No. E/MD/AK/2025. Dt.
 For Rs. 103872/- (One lakh three thousand Eight Hundred Seventy two only)

Estimate Prepared By

(D.M. Muckute)
 Sectional Engineer

Estimate checked by

(S.V. Nirkhe)
 Deputy Engineer
 Gate Mfg & Erection Sub Div No.1
 Akola

Executive Engineer
 Mechanical Division
 Akola