महाराष्ट्र शासन
जलसंपदा विभाग

कार्यकारी अभियंता यांचे कार्यालय,

पत्ता : कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, सदर , नागपूर

E-mail :eemewdngp@yahoo.in Phone No. 0712-2981048

निवीदा सुचना क्र. – ७/ सन २०२५-२६

महाराष्ट्र राज्याच्या राज्यपालांच्या वतीने कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, सदर , नागपूर , महाराष्ट्र शासन हे सक्षम निविदाकारांडुन खालील कामाकरीता निविदा मागवित आहे. महाराष्ट्र शासन जलसंपदा विभाग शासन निर्णय क्रमांक संकिर्ण/१११७/प्र.क्र.१०४/१७/यांत्रिकी दिनांक १४.०३.२०१८ अन्वये खालील कामांकरीता निविदा सादर करणारे कॅत्राटदार, जलसंपदा विभागातील यांत्रिकी संघटनेकडे पंजिकृत असणे आवश्यक नाही. सदर निविदा सूचना जलसंपदा (यांत्रिकी) विभागाच्या वेबसाईटवरील क्र. www.mahayantriki.gov.in या संकेस्थळावर बघावयास मिळेल. निविदा स्वीकारण्याचा अथवा नाकारण्याचा अधिकार **कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर** , यांनी राखुन ठेवला आहे. अट असलेली निविदा स्वीकारली जाणार नाही.सदर निविदा सुचनेमध्ये काही बदल होत असल्यास विभागीय कार्यालयाच्या सुचना फलकावर / www.mahayantriki.gov.in उपलब्ध करुन देण्यात येईल.

अ. क्र.	कामाचे नाव	अंदाजीत निविदा किंमत (जीएसटी वगळून)	बयाना रक्कम	कोरी निविदा प्रपत्राची किंमत	काम पूर्ण करण्याचा कालावधी
१	पाटबंधारे उपविभाग, **आर्वी अंतर्गत सांवगी** लधु प्रकल्पाचे द्वार आकार 0.9 x 0.9 मी. -१ नग दुरुस्ती करणे	2,14,329/-	2,150/-	1,000/-	१ महिना
२	पाटबंधारे उपविभाग, **आर्वी अंतर्गत लहादेवी** लधु प्रकल्पाचे द्वार आकार 0.9 x 0.9 मी. -१ नग दुरुस्ती करणे	2,60,398/-	2,610/-	1,000/-	१ महिना

कोरी निवीदा प्रपत्राची किंमत Rs. १,००० /- (रु. १८०/- Goods and Services Tax (GST) भरणा केलेली पावती निविदा उघडण्याचा दिवसापर्यंत कार्यालयात जमा करणे बधंनकारक राहिल. अन्यथा लिफाफा क्र. १ मध्ये अपात्र करण्यात येईल.)

जिल्हा : वर्धा जिल्हा

निविदा विक्रीचा कालावधी :- दि. १३.०६.२०२५ (११.०० वाजेपासून) ते दि. २०. ०६.२०२५ (१८.०० वाजेपर्यंत)

निविदा सादर करण्याचा अंतिम कालावधी :- दि.१३.०६. २०२५ (११.०० वाजेपासून) ते दि. २३.०६.२०२५ (१८.०० वाजेपर्यंत)

निविदा उघडण्याचा कालावधी :- दिनांक २४.०६.२०२५ १४.०० पासून

कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर यांच्या कार्यालयात.

जा.क्र. १२९८ /लेखा शाखा.२/निवीदा सुचना क्र.७ /२०२५-२६

कार्यालय,
कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा,
विभाग, नागपूर
दिनांक : 23/6/2025

(वि.रा.प्रधान)
कार्यकारी अभियंता
यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग,
नागपूर

प्रत - मा. अधीक्षक अभियंता, यांत्रिकी मंडळ, नागपूर यांना माहितीसाठी सविनय सादर.
प्रत – भांडारा शाखा / विभागीय कार्यालय सुचना फलकावरील व्यापक प्रसिध्दीसाठी.

G:\RNF\Account Section\Booklet\Booklet 2025-26\E-Tender Notice lr.2025-26.doc20

Scanned by CamScanner

Repairing of Head Regulator Gate 0.9x0.9 mtr- 1 No.@ Lahadevi M. I. Tank under Executive Engineer, Wardha Irrigation Division, Wardha

Sr.No.	Description	Quantity		Rate	Amount
	ABSTRACT				
1	Manufacturing, Providing and supplying G. M. Nut (Main portion of Stem Nut- OD 98 mm ID 45 mm Ht. 214 mm, Collar- OD 137 mm ID 98 mm Ht. 20 mm)) (Ref. RA 1)	1.00	No	15504.581	15504.581
2	Manufacturing, Providing of Thrust Ball Bearing for 8 MT Screw stem Hoist (Ref. RA 2)	1.00	No	34046.171	34046.171
3	Fabrication, Erection & Painting of Ladder in Well (Ref. RA 3)	1.00	No	35210.639	35210.639
4	Fabrication, Erection & Painting of Conduit Pipe Net (Ref. RA 4)	1.00	No	10810.472	10810.472
5	Fabrication, Erection & Painting of Walk Way Bridge (Ref. RA 5)	1.00	No	124999.011	124999.011
6	Greasing of Square Threaded & V- threaded Stem Rod (Ref. RA 6)	1.0	No	2473.490	2473.490
7	Greasing of Stem Nut (Ref. RA 7)	1.0	No	2957.280	2957.280
8	Surface Preparation, Providing & Applying Primer Red Oxide Paint in two coats & anticorrosive coal tar black paint IS 290-1961 in two coats to Walk way Bridge, Well Railing, Well Top Net Grill, Hoist, Sleeve Girder (Ref. RA 8)	24.620	Sqm	8753.670	8753.670
9	Rental charges for supplying & maintaining 230/415 V, 50 cycles AC generating set 3 to 10 kVA capacity with necessary fuel, mains, switchgears and accessories complete with continuous running on load/no load as per requirment for repair Head Regulator gate 0.9 x 0.9 mtr @ Lahadevi M. I. Tank. (Ref. RA 9)	3.00	Days	15300.198	15300.198
10	Transportation from Wardha to Lahadevi Project Site by Tata 407 Tempo @ 32 per km (Ref. RA10)	2.00	Trip	5171.200	10342.400
				TOTAL CHARGES :-	**260397.912**
				Add 1% Insurance charges:	**2603.979**
				Gst 18 %:-	**46871.624**
				Total chrages	**309873.515**
				Say Total chrages	**309874.000**

Estimate Prepared by me

S. M. Karambe
Sect. Engineer

Deputy Engineer
Mechanical Engineering Workshop
Sub Divison No 3, Wardha

Sanction Estimate No. 11 /2025-26
MEW DN./NGP/TS/Dt. 28/05/2025 Sanctioned
for Rs. 309874/- (Rs. Three Lakh Nine thousand Eight chundred & Seventy four only

Executive Engineer
Mechanical Engineering Workshop
Division, Sadar, Nagpur

Scanned by CamScanner

Repairing of Head Regulator Gate 0.9x0.9 mtr- 1 No.@ Sawangi M. I. Tank under Executive Engineer, Wardha Irrigation Division, Wardha

Sr.No.	Description	Quantity		Rate	Amount
	ABSTRACT				
1	Dismantling of Sliding type Gate leaf of size 0.9 x 0.9 Mtr / 1.2 x 1.2 Mtr (7.2 to 12 MWH) and hoist assembly - 1 No. lifting of the same up-to Platform for Repair work and lowering on Sill Beam. Complete job including cost of sundry material and labour charges, with leads & lifts at site etc complete. (Ref. RA 1)	1.00	No	23620.870	23620.870
2	Replacement of Stem rod with New one of 50 mm dia -3Mtr long -3 nos with flanges of size 0.90 x 0.90 Mtr Complete including cost of material and machining charges. (Total Wt. 123.684 kg) (Ref. RA 2)	1	No	15810.750	15810.750
	Fabrication of Stem Rod Assly.				
	Square Threaded Stem Rod Ø 50mm L-3000 mm — 1				
	Intermediate stem Rods Ø 50mm L-3000 mm — 1				
	Plates For Flanges Male & Female 250x250x20mm — 4				
	Stiffner for flanges - tringular 100x80x12mm — 16				
	Plate 10 mm thk cut to Stem Nut key 16x60x10 — 1				
	M. S. Nut- Bolt M-16 x 100 mm for flanges & Well net. Weight= 0.270kg /No= 24 x0.270 = 6.48 kg				
3	G. M. Nut (Main portion of Stem Nut- OD 85 mm ID 32 mm Ht. 214 mm, Collar- OD 124 mm ID 85 mm Ht. 20 mm), Thrust Ball Bearing No.51217 - 2nos (Ref. RA 3)	1.00	No	32342.877	32342.877
4	Fabrication, Erection & Painting of Ladder in Well (Ref. RA 4)	1.00	No	24424.756	24424.756
5	Fabrication, Erection & Painting of Conduit Pipe Net (Ref. RA 5)	1.00	No	10810.472	10810.472
6	Greasing of Square Threaded & V- threaded Stem Rod (Ref. RA 6)	1.000	No	2473.490	2473.490
7	Greasing of Stem Nut (Ref. RA7)	1.000	No	2957.280	2957.280
8	Surface Preparation, Providing & Applying Primer Red Oxide Paint in two coats & anticorrosive coal tar black paint IS 290-1961 in two coats to Walk way Bridge, Well Railing, Well Top Net Grill, Hoist, Sleeve Girder (Ref. RA 8)	51.133	Sqm	18181.010	18181.010
9	Rental charges for supplying & maintaining 230/415 V, 50 cycles AC generating set 3 to 10 kVA capacity with necessary fuel, mains, switchgears and accessories complete with continuous running on load/no load as per requirment for repair Head Regulator gate 0.9 x 0.9 mtr @ Sawangi M. I. Tank. (Ref. RA9)	3.00	Days	15300.198	15300.198
10	Cleaning of HR Gate size 0.9 x0.9 mtr slot -1 No at Sawangi MI tank . (Ref- RA-10)				
	Under Water Inspection Charges per day including cost of material, sundry material and labour charges etc. as per drawings, specifications and or instructions of concern in charge. Under Water Inspection Charges using divers upto 25 Mtr depth.	1.00	Day	60650.50	60650.50
11	Transportation from Wardha to Sawangi Project Site by Tata 407 Tempo @ 32 per km (Ref. RA 11)	2.00	Trip	3878.400	7756.800
				TOTAL CHARGES :-	**214329.004**
				Add 1% Insurance charges:	**2143.290**
				Gst 18 %:-	**38579.221**
				Total chrages	**255051.514**
				Say Total chrages	**255052.000**

Estimate Prepared by me

S. M. Karambe
Sect. Engineer

Sanction Estimate No. 17/2025-26
MEW DN./NGP/TS/Dt. 02/06/2025 Sanctioned
for Rs. 255052/- (Rs. Two lakh fifty five thousand & fifty two)

Executive Engineer
Mechanical Engineering Workshop

Deputy Engineer
Mechanical Engineering Workshop
Sub Divison No 3, Wardha

Scanned by CamScanner