



महाराष्ट्र शासन
जलसंपदा विभाग

कार्यकारी अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग,
लिंग रोड, सदर, नागपूर
दूरध्वनी क्र. ०७१२-२९८१०४८ Email- eemewdngp@yahoo.in

निविदा सुचना क्रमांक ३ सन २०२४-२५

अभियंता, यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग, नागपूर (दूरध्वनी क्र.०७१२-२५२२४२५) हे महाराष्ट्र शासन जलसंपदा विभागाच्या वतीने खालील कामासाठी ब-१ (टक्केवारी दराने) निविदा <http://mahyantriki.gov.in> या संकेतस्थळावरून मागवित आहे. महाराष्ट्र शासन जलसंपदा विभाग शासन निर्णय क्रमांक संकिर्ण/१११७/प्र.क्र.१०४/१७/यांत्रिकी दिनांक १४.०३.२०१८ अन्वये खालील कामांकरीता निविदा सादर करणारे कंत्राटदार, जलसंपदा विभागातील यांत्रिकी संघटनेकडे पंजिकृत असणे आवश्यक नाही.

| अ.क्र. | कामाचे नाव | अंदाजीत निविदा किंमत (जीएसटी वगळून) |
|--------|--|--|
| १ | Applying cardium compound , replacement of oil & greasing of components of radial gate of size 12 x 6.5 mtr and maintenace of DG set @ Nand Dam Lower Venna Project Dist Nagpur under Eexecutive Engineer, Nagpur Irrigation Division (South) Nagpur . (Rs.259778/-) | रु. २,५९,७७८ /- |

निविदा उपलब्ध कालावधी :- दिनांक १०/०६/२०२४ ते दिनांक २१/०६/२०२४

निविदेतील GEO-Tagging कालावधी :- दिनांक ११/०६/२०२४ ते दिनांक १४/०६/२०२४ व
दिनांक १८/०६/२०२४

निविदा सादर करण्याचा कालावधी- १०/०६/२०२४ ते दिनांक २४/६/२०२४

निविदा उघडणे :- दिनांक २६/०६/२०२४

खालील संकेतस्थळावर ई-निविदा बाबत सर्व माहिती उपलब्ध आहे.

1. <http://mahyantriki.gov.in>

(सदर निविदेसुचनेमध्ये काही बदल होत असल्यास वरील वेबसाईटवर व कार्यालयाच्या सुचनाफलकावर प्रसिध्दी करण्यात येईल)

Sd/-

(वि.रा.प्रधान)

कार्यकारी अभियंता

यांत्रिकी अभियांत्रिकी कर्मशाळा विभाग,

नागपूर

जा.क्र. १२२२ /निविदा /लेशा/२०२४ दिनांक ७/६/२०२४

कार्यकारी अभियंता यांत्रिकी अभियांत्रिकी कर्मशाळा यांचे कार्यालय सदर, नागपूर

ABSTRACT

Cardium compound, replacement of oil & greasing of components of radial Gate of size 12x6.5 mtr and
 ance of DG Set @ Nand Dam Lower Venna Project Dist - Nagpur under Executive Engineer, Nagpur Irrigation
 (South), Nagpur.

| Description | Qty | Unit | Rate | Unit (Rs/Job) | Amount |
|--|-----|------|----------------------------------|---------------|----------------------------------|
| 1 | | | | | |
| Repair and schedule maintenance of New T.M.T.L. Make 62.5 KVA DG Set at Nand Project. <i>As Per Rate Analysis - 1</i> | | | | | |
| Supplying and erecting lub oil filter element along with sealing rings, gasket etc complete suitable for DG Set | | | | | |
| Supplying and erecting fuel filter along with sealing rings, gasket, primary filter and water separator etc complete suitable for DG Set | 1 | no. | 12693.78 12695.00 | Rs/no. | 12693.78 12695.00 |
| Supplying and erecting Air cleaner/Air filter element suitable for DG set | | | | | |
| Topping up new glycol based coolant 50/50 with operating range from 118°C to -37°C of approved make | | | | | |
| Topping up new lubricating oil 15W/40 grade of approved make as per IS 13656 : 2014 | | | | | |
| 2 | | | | | |
| Repair and schedule maintenance of Old 62.5 KVA DG Set at Nand Project. <i>As Per Rate Analysis - 2</i> | | | | | |
| Supplying and erecting lub oil filter element along with sealing rings, gasket etc complete suitable for DG Set | | | | | |
| Supplying and erecting fuel filter along with sealing rings, gasket, primary filter and water separator etc complete suitable for DG Set | 1 | no. | 12695.00 12693.78 | Rs/no. | 12695.00 12693.78 |
| Supplying and erecting Air cleaner/Air filter element suitable for DG set | | | | | |
| Topping up new glycol based coolant 50/50 with operating range from 118°C to -37°C of approved make | | | | | |
| Topping up new lubricating oil 15W/40 grade of approved make as per IS 13656 : 2014 | | | | | |
| 3 | | | | | |
| Removing Old Cardium Compound of Wire rope of 36 MT cap hoist - 1 No by cleaning agent & Applying new Cardium Compound (Servocoat 140) - 16 Kg., including cost of material, sundry material and labour charges etc as per drawings, specifications and or instructions of concern in charge <i>As Per Rate Analysis - 3</i> | 7 | no. | 11830.897 11713.76 | Rs/no. | 82816.279 81996.35 |

| | | | | | | |
|---|---|------|--------------------------------------|---------|--|------------------|
| <p>ing of Old Oil from RGB & filling with Gear oil GX-90 - 11 cleaning Gear train by removing old Grease & Applying Grease grade no. 150 - 15 Kg to Gear train, Pedastal, um axle, Trunion pin, Locking box etc. and refilling of oil of dial gate of 36 MT cap hoist -1 No., including cost of terial, sundry material and labour charges etc as per wings, specifications and or instructions of concern in rge. <i>As Per Rate Analysis - 4</i></p> | 7 | no. | <p>18689.04 <u>18504.00</u></p> | Rs/no. | <p>130823.28 <u>129528.00</u></p> | |
| <p>eaning of Drain Holes of Horizontal girder, End arm embly, Locking box etc, of R.G. 12 x 6.5 m - 1 No by way of moving rust, dust slurry, any other foreign particles etc. , luding cost of material, sundry material and labour charges . as per drawings, specifications and or instructions of ncern in charge. <i>As Per Rate Analysis - 5</i></p> | 7 | no. | <p>1727.1 <u>3179.26</u></p> | Rs/no. | <p>12089.7 <u>22254.79</u></p> | |
| <p>ansportation of Fabricated Material by 4MT cap tempo. <i>As er Rate Analysis - 6</i></p> | 2 | Trip | 4329.53 | Rs/Trip | 8659.05 | |
| 259778.309 | | | | | Grand Total :- | <u>267825.75</u> |