

# GOVERNMENT OF MAHARASHTRA

## Water Resources Department Budgetary Offer No. 01/2023-24

Executive Engineer, Vishnupuri Pump House Division Nanded (vphdn@rediffmail.com) invites budgetary offer for the Estimation Purpose from reputed & experienced company/authorized dealer for following work. The offer of each should be inclusive of all taxes, freight & duties. The offer should reach to this office on or before dated 01/01/2024. Please note budgetary offer is invited only for the estimation purpose & it does not give any assurance regarding floating of tenders or otherwise.


### SCHEDULE

**Subject:** - Providing complete inspection, repairing & testing of 6.6KV H.T. panel, LT Panel at Shankarraoji chavhan Vishnupuri Lift Irrigation Scheme, Tq. Dist.Nanded.

Sr. No.	Description of Items	Qty	Unit
1	<p><b>Item No. 1:-</b>Complete inspection of 6.6KV H.T. panel including complete checking of all control wiring, checking of all relays of panel, Resetting of relay parameter if necessary and complete Relay Calibration Test. Checking complete operating mechanism of VCB on remote as well as on manual mode, checking &amp; resetting of timer circuit. Test &amp; trial operation of breaker on test &amp; service mode. Minor replacement of spare part if necessary &amp; Servicing of all VCBs &amp; CT,PT, Contactors. All necessary testing's related to H.T. Panel Necessary Painting at Burn Out Places and Complete Earth Fault Testing.</p> <p>H.T.panel has following feeders.</p> <ol style="list-style-type: none"><li>1) Incomer-2-nos.</li><li>2) Bus coupler - 1 no.</li><li>3) Motor feeders - 14 no.</li><li>4) Capacitor feeders - 2 no.</li><li>5) Spare feeders - 1 no.</li><li>6) Auxiliary Transformer Feeder -1 no.</li></ol>	1	No.
	<p><b>Item No.2:-</b> Complete inspection of 415V, 400A LT panel including complete checking of all control &amp; Power wiring, checking of all relays of panel, Resetting of relay parameter if necessary and complete Relay Calibration Test. Checking complete operating mechanism of ACB &amp; trial operation of breaker on test &amp; service mode. Minor replacement of spare part &amp; Fuses if necessary &amp; Servicing of all ACB, SFU &amp; CT, PT, Contactors. All necessary testing's related to L.T. Panel Necessary Painting at Burn Out Places and Complete Earth Fault Testing.</p> <p>L.T.panel has following feeders.</p> <ol style="list-style-type: none"><li>1) Incomer ACB 415V, 400A - 2 nos.</li><li>2) Outgoing Feeders (32A.63A.100A)-12nos.</li></ol>	1	No.

**Note:** All applicable taxes/charges should be separately mentioned.

  
Executive Engineer

 Vishnupuri Pump House Division  
Nanded.

Out W. No. VPHDN/TenderSec/ 1512/Year 2023-2024

Date: 08/12/2023

**Copy to:** The Superintending Engineer, Mechanical Circle, Nanded for favor in information  
Please.