

जा.क्र./द्वानिवउवि.१/अम/ताशा-१ / २५१२ /सन-२०२०	कार्यालय- कार्यकारी अभियंता, द्वार निर्मिती व उभारणी विभाग क्र.१, जेल रोड, अमरावती - ४४४६०२
फोन नं. ०७२१-२६६१४५१	
फॅक्स नं. ०७२१-२६६१४५१	
ई.मेल- eegatediv1amt@gmail.com	दिनांक - ५/११/२०२०

प्रति,

उप अभियंता,  
द्वार उभारणी व दुरुस्ती उपविभाग क्र.२,  
खामगाव.

**विषय :**

**संदर्भ :**

- खडकपूर्णा प्रकल्पावरील स्टार्टर व कनोपी दुरुस्ती अंदाजपत्रक मंजुरीकरिता सादर करणेबाबत..
- उपविभागीय अधिकारी, खडकपूर्णा प्रकल्प व्यवस्थापन उपविभाग, देऊळगाव मही, यांचे पत्र क्र.252/2020 दि. 20/08/2020.
  - उप अभियंता, द्वार उभारणी व दुरुस्ती उपविभाग क्र.२, खामगाव यांचे पत्र क्र. 324/2020 दि. 13/10/2020
  - विभागीय कार्यालयाचे जा.क्र. द्वानिवउवि1/अम/ताशा1/निरीक्षण टिप्पणी/2486/2020 दि.03/11/2020 कार्यकारी अभियंता, द्वार निर्मिती व उभारणी विभाग क्र.१, अमरावती यांची प्रकल्प भेट दि. 30/10/2020 रोजीची निरीक्षण टिप्पणी.

-०००-

उपरोक्त संदर्भिय पत्रान्वये सादर करण्यात आलेल्या अंदाजपत्रकास महाराष्ट्र शासन सार्वजनिक बांधकाम नियम पुस्तिका 1984 मधील परिशिष्ट 42 अ.क्र. 57 परिच्छेद क्र. 392 तसेच जलसंपदा विभाग शा. परिपत्रक क्र. संकिर्ण 1018(प.क्र. 109/2018) यांत्रिकी, दि. 07/08/2019 अन्वये प्रदान केलेल्या अधिकारा अंतर्गत खालील प्रमाणे संभाव्य खर्चाच्या अंदाजपत्रकास मंजुरी प्रदान करण्यात येत आहे.


अ.क्र.	अंदाजपत्रकाचा तपशिल	तांत्रिक मंजुरी प्रदान करण्यांत आलेली रक्कम	अंदाजपत्रक मंजुरी नोंदवही क्रमांक	लेखा उपशिर्ष
१	२	३	४	५
१	खडकपूर्णा प्रकल्पावरील स्टार्टर व कनोपी दुरुस्ती कामे.	रु.२२५६६६/-	अ.प.क्र./१४९/२०२० ता.-१ दि.०३/११/२०२०.	4701-मोठे व मध्यम प्रकल्प या वरील भांडवली खर्च जमा ठेव, कार्यकारी अभियंता, बुलढाणा पाठबंधारे विभाग, बुलढाणा यांचे कडून देय.

कामे करून घेतांना खालील अटीचे काटेकोरपणे पलन करावे.

- खात्याअंतर्गत साहित्य उपलब्ध नसल्याची खात्री केली आहे.
- मंजुर अंदाजपत्रकीय रक्कमेपेक्षा कामांवर जास्त खर्च होणार नाही याची दक्षता घ्यावी.

- ३) केलेल्या कामाची कार्यक्षमता, अनुकूलता, परिपूर्णता, तत्परतेने नोंदी घेण्यात याव्यात. त्या अनुषंगाने तसा अहवाल वेळोवेळी सादर करण्यात यावा.
- ४) अंदाजपत्रकामध्ये नमुद कामे प्रचलित शासकिय नियमानुसार करुन घेण्यात यावे.
- ५) सदर कामे करतेवेळी जर विभागाची यंत्रसामुग्री तसेच साहित्य वापरात असल्यास त्याचे भाडे व किंमत वसुल करण्यात यावी.

सहपत्र :- अंदाजपत्रकाची मंजुर प्रत.

  
कार्यकारी अभियंता,  
व्दार निर्मिती व उभारणी विभाग क्र.१,  
अमरावती.  
०१६

प्रत - मा. अधीक्षक अभिंता, यांत्रिकी मंडळ नागपुर यांना माहितीस्तव सविनय सादर.

प्रत - निविदा शाखा, विभागीय कार्यालय यांना माहिती करिता अग्रेषित

सहपत्र :- मंजुर अंदाजपत्रकाची छायांकित प्रत.

Estimate Prepared in the Office of Deputy Engineer Gate Erection And repair Sub Div No 1 Khamgaon To Meet Probable Expendature of supplying and installing of New Starter 6 nos to Radial Gate size 12x8 mtr no 04 ,05,06,08,09 012,13,18 and 19 and 2 Starter extra and Brake Coil replacement for gate no 1, 5,,14,17 and 2 Coil Extra For Emergency at Khadakpurna project

**ABSTRACT**

Qty	Unit	Description	Rate	Per	Amount
11	Job	1) Supplying and Erecting of starter to Gate No04 ,05,06,08,09 012,13,18 and 19 and 2 Starter extra of Khadakpurna Project 24 to 40 Amp (20 Hp ) Including FittingCharges And trial. ( DSR Sheet Attached )	14408.00	Job	158488.00
20	Miter	2) Supplying , erecting and Terminating XLPE armoured cable 3 core 2.5 sq mm copper conductor continuous 5.48 sqmm (12 SWG) GI earth wire complete erected with glands and lugs on wall /truses/pole or laid in provided trench /pipe as pfer specification CB-LT/CU( For Fitting of Starter and Motor ) As pwd Electrical DSR	205.00	Miter	4100.00
6	Job	3) Job work of Providing and rewinding of the electromagnatic type brake coil suitable to operate 110V DC supply by superior quality enamel lled copper wire of require size complete testing to radial gate no 1, 5,,14,17 and 2 Coil Extra For Emergency- by new one of 105 MT capcity Hoist of radial gate complete Job With Material And labour rate Asper PWD Electrical DSR	4392.00	Job	26352.00
1	Job	4) Transportation Charges From Khamgaon to Khadakpurna Project 4T Mini Tempo	<del>12031.00</del> 10012	Job	<del>12031.00</del> 10012.00
		Total as per PWD Electrical DSR			30452.00
		Total as per mechanical DSR			<del>170519.00</del> 168500.00
		Add 1 % WCC to Starter and Transportationas per Mechanical CSR			<del>1705.19</del> 1685.00
		Total as per mechanical DSR Includind WCC 1%			<del>172224.19</del> 170185.00
		Add 0.5 % Insurance to Starter and Transportationas per Mechanical CSR			<del>861.12</del> 250.92
		Total as per mechanical DSR Including WCC 1%and insurance0.5%			<del>173085.31</del> 171035.92
		Gross Total			<del>203537.31</del> 201487.92

Add 12% GST

24424.48


Total

227962.00

24178.55  
225666.47  
Scg = 225666/-

**Certificates :**


- 1) The Rate of Materials are as per the Mechanical DSR
- 2) The required Materials and skilled labours for such type of work are not available within the division, Hence the above work is proposed for outside agency.
- 3) Schedule of Rates are Approved by Chief Engineer (Mechanical), WRD, Nashik by Vide Letter .is taken into consideration for framing this estimate.

  
(S.V. Nirkhe)  
Deputy Engineer  
Gate Erection & Repairs  
Sub-Dn. No. 2, Khamgaon.

Estimated No. 149 /E.E/GMEE D-1-A/19

03/11/2010 Technically Sanctioned For Rs 225666/-

Rs. Two lakh twenty five thousand  
six hundred and sixty six only

  
Executive Engineer  
Gate Manufacturing & Erection  
Division No.1, Amravati