


ABSTRACT

NAME OF WORK :- Supply, Erection, Testing & Commissioning of UG Cable at Jamkhurd LIS, Ta-Pombhurna,
Dist- Chandrapur

Item No.	Qty	Description of Items	Rate	Unit	Amount
1	50	Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 3½ core 300 sq. mm. aluminium conductor complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/ALHighlight Compensation	1717.8 ✓	Mtr	85890 ✓
2	10	Supplying & erecting G.I. pipe 'A' class 75 mm dia. erected for enclosing XLPE armoured cable on wall/pole as per specification no. CB-CE	705.6 ✓	Mtr	7056 ✓
3	40	Supplying and laying (including excavation of suitable width & depth up to 90 cm) 120 mm outside dia. double wall corrugated pipes (DWC) of HDPE for enclosing cable below ground/road surface, to required depth	411.6 ✓	each	16464 ✓
Total Rs. =					109410 ✓
Add 18% GST Rs. =					19693.8 ✓
Sub-Total Rs. =					129103.8 ✓
Add 3% Contingences Rs. =					3873.114 ✓
Grand Total Rs. =					132976.9 ✓
(Amount in words Rs. One lakh Thirty Two Thousand Nine Hundred Seventy Seven only)					

(Amount in words Rs. one lakh twenty nine thousand one hundred four only) say total :- 129104

Prepared By:-



(N.K. Pathade)
AE-2

Checked By :-



(S.S. Bageshwar)

Deputy Engineer

Lift Irrigation Mechanical & Electrical

Sub-division No.2, Chandrapur

Sanctioned Estimate No. 63 Year 2025-26 Dt. 15-10-2025

Amount Rs. 129104 In Words one lakh twenty nine thousand one hundred four only


Executive Engineer
Mechanical Lift Irrigation Division No. 2
Chandrapur