



महाराष्ट्र शासन जलसंपदा विभाग
कार्यकारी अभियंता, मुख्य द्वार उभारणी पथक क्र.5,
दिंडोरी रोड, नाशिक-422004



कार्यालय दूरध्वनी क्रं- (0253) 2970339

Email - cgeu5nsk@gmail.com

जा.क्र.मुद्दाउप-५/तांशा-२/१५४४/२०२४

दि: २५/११/२०२४

प्रति,
निविदा शाखा,
मुख्य द्वार उभारणी पथक क्र.5,
नाशिक.04

विषय:- मा. अधीक्षक अभियंता, यांत्रिकी मंडळ, नाशिक कक्षात नविन वातानुकूलीत यंत्राणा बसवून कार्यान्वित करणे खर्चाचे अंदाजपत्रक मंजूरीबाबत.

उपरोक्त विषयान्वये मा. अधीक्षक अभियंता, यांत्रिकी मंडळ, नाशिक कक्षात नविन वातानुकूलीत यंत्राणा बसवून कार्यान्वित करणे खर्चाचे अंदाजपत्रक तयार करण्यांत आले आहे. सदर अंदाजपत्रकातील दर हे PWD DSR 2022-23 अनुषंगाने घेण्यात आले आहे.


कामाचे नाव - मा. अधीक्षक अभियंता, यांत्रिकी मंडळ, नाशिक कक्षात नविन वातानुकूलीत यंत्राणा बसवून कार्यान्वित करणे खर्चाचे अंदाजपत्रक मंजूरीबाबत.

तांत्रिक मंजूरी प्रधान करण्यात आलेली अंदाजपत्रकाची मंजूर रक्कम रु. १,९०,१८०/- (with GST) इतकी आहे. सदर मंजूरी या कार्यालयाच्या नोंदवहीतील बाब अनुक्रमांक अन्वये मंजूर करण्यात आलेले आहे.

अटी :-

1. कोणत्याही परिस्थितीत शासनाचे आर्थिक नुकसान होणार नाही याची दक्षता घेण्यात यावी.
2. सदर अंदाजपत्रकात दर व परिमाण याबाबत उपअभियंता यांनी स्वतः खात्री केली आहे.
3. सदरची कामे शासकीय प्रचलित निर्णयानुसार नियमानुसार व आदेशानुसार करण्यात यावी.
4. सदर अंदाजपत्रकात मंजूर करण्यात आलेले दर हे या अंदाजपत्रकापुरतेच मर्यादित राहतील.

सोबत :- मंजूर अंदाजपत्रक


(डॉ. श. ना. जोशी)
कार्यकारी अभियंता,
मुख्य द्वार उभारणी पथक क्र.५,
नाशिक

Name of Work: -Supplying and Erecting Split Type Air Conditioner 2 Nos. and Other allied Works @ SE Mechanical Office Nashik.

Abstract					
Sr.No.	Unit	Qty	Description	Rate	Amount
1	Nos	2	Supplying, installing, testing & commissioning split type variable speed inverter technology with minimum 3 to 1 convertible mode for compressor, room air conditioning unit 1.3TR to 1.6TR capacity having ISEER minimum 5.00 suitable to operate on 250V, 50 Hz, A.C. supply having 1 no of air handling unit hi-wall/floor mounting type complete with refrigerant R32 having copper condenser, minimum 2.5PM filter, self diagnosis feature, stabilizer free operation & temperature display on indoor unit, noise level maximum 50dBA at position. As per PWD Electrical DSR 2022-2023. Item No.3-2-11.Rate is 55578.00	55578	111156
2	Meters	20	Supplying & erecting seamless outside & inside, smooth, dry and clean copper pipe with ROHS compliant suitable for refrigerant having 22SWG thickness and inner dia/size 22mm complete. As per PWD Electrical DSR 2022-2023. Item No.3-2-28.Rate is 636.00	636	12720
3	Meters	20	Supplying and erecting HMS PVC conduit 25mm dia. with PVC accessories on wall/ceiling. As per PWD Electrical DSR 2022-2023. Item No.1-2-4.Rate is 96.00	96	1920
4	Meters	20	Supplying & erecting mains with 3x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places. As per PWD Electrical DSR 2022-2023. Item No.1-3-6.Rate is 93.00	93	1860
5	Nos	2	Point wiring for independent plug, concealed type in min 20 mm HMS PVC conduit with 1.5 sq.mm (2+1E) FRLSH grade copper wires, modular type switch and socket, earthing and required accessories. As per PWD Electrical DSR 2022-2023. Item No.1-7-8.Rate is 781.00	781	1562
6	Nos	1	Supplying, installing and testing earthing with copper earth plate size 60 x 60 x 0.315 cm with funnel with a wire mesh for watering and brick masonry block C.I. cover with minimum 25 kg Carbon based environment friendly back fill ground enhancing compound complete with all accessories of copper materials & recording the results. As per PWD Electrical DSR 2022-2023. Item No.9-1-6.Rate is 15734.00	15734	15734
7	Nos	2	Dismantling the existing split type air conditioner of any type and capacity safely without any damages and making the site clear. As per PWD Electrical DSR 2022-2023. Item No.3-12-3.Rate is 885.00	885	1770
8	Nos	1	Supplying pedestal type air circulator 450 mm. sweep oscillating type suitable to work on 230 Volts 50 cycles 1440 RPM without speed regulator, metallic blades, overheat protection unit, totally enclosed, flame proof motor with additional 3 core wire, 5 metre length and hand shield type 3 pin 5A. plug top complete with moisture proof treatment and 'E' class insulation.As per PWD Electrical DSR 2022-2023. Item No.2-10-8.Rate is 5030.00	5030	5030
			Add GST@ 28% on Item no.1	Total:-	151752
			Add GST @ 18% on Items no.2 to 8	@28%	31124
				@18%	7307
				Grand Total	190183
				Say	190180

In words Rs. One lakh Ninty thousand One hundred & eighty seven only

The rates are taken As per PWD Electrical DSR 2022-2023


S.B. Wagh
Sect Engr.


S.D. Narkhede
Chief Gate Erection Unit
No. 5, Nashik-4

Technically sanctioned for Rs. ~~82600/-~~ (One lakh Ninty thousand One hundred Eighty or Rs. Eighty Two Thousand Six Hundred Only.) vide this office No.T&p/
190,180/- /2024 dt. / /2024 /Tech-


(Dr. S.N. Joshi)
Executive Engineer,
Chief Gate Erection Unit No.5,
Nashik